

# CONCRETE

## AND

# CONSTRUCTIONAL ENGINEERING

OCTOBER, 1951.



Vol. XLVI, No. 10

FORTY-SIXTH YEAR OF PUBLICATION

PRICE 1s. 6d.

ANNUAL SUBSCRIPTION 12s., POST FREE. \$3.00 in Canada and U.S.A.

### LEADING CONTENTS

	PAGE
Proposed Metric System in Great Britain . . . . .	293
The Ultimate Resistance of Prestressed Concrete Beams. By Dr. P. W. Abeles . . . . .	295
Construction of a Large Jetty on Southampton Water . . . . .	305
Coast Protection Works at Clacton . . . . .	316
Composite Trussed Beams . . . . .	320

No. 527.

ISSUED MONTHLY

Registered for  
Canadian Magazine Post

## BOOKS ON CONCRETE

For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:  
CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., WESTMINSTER, S.W.1



*For over 60 years*

this trade mark has stood for speed and  
strength in reinforced concrete work.

# DRAGON

(Brand)

## PORTLAND CEMENT

*Supplied by*

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.  
PENARTH, SOUTH WALES

Telephone : Penarth 300

Telegrams : "Cement, Penarth"

# Burton's

(SAFETY LOCK—UNIQUE FEATURE)

## TUBULAR STEEL PROPS (ADJUSTABLE)

*For Supporting Temporary Floor Shuttering*

### Burton's Adjustable Tubular Steel Props

for the above and many other purposes, are much preferred by the men who erect them to the old-fashioned Timber Props. They can be erected by one man in a few minutes and positively adjusted and **safely locked** in position, thus avoiding any possibility of being accidentally or maliciously tampered with.

*Manufactured in our own most modern and up-to-date works at Old Hill, Staffs.*

No spanner, jack, or tommy bar necessary; simply lift inner tube, insert peg, and tighten up.

*No loose parts to lose, and easily transported.*

### BURTON'S ADJUSTABLE TUBULAR STEEL BEAM PROPS

are provided, as illustrated, with a braced head for supporting temporary shuttering to R.S.J. casings and reinforced concrete beams, &c.

Size No.	HEIGHT		Approx. Weight each in Lb.
	Fully Closed	Fully Extended	
1.	5 ft. 7 in.	9 ft. 10 in.	50
2.	6 ft. 7 in.	10 ft. 10 in.	54
3.	8 ft. 2½ in.	12 ft. 5½ in.	58
4.	11 ft. 0 in.	16 ft. 0 in.	72



*Head Fittings to suit any Special Job, designed for use with BURTON'S PROPS.*

## Burton's Patent Solid Dropforged Steel Scaffolding Fittings

## THE LONDON & MIDLAND STEEL SCAFFOLDING CO., LTD.

ST. LUKE'S WORKS, OLD HILL, STAFFORDSHIRE

Telegrams: DUBELGRIP, CRADLEY HEATH.

Telephone: CRADLEY HEATH 6237/8

London Offices: BURWOOD HOUSE, CAXTON STREET, S.W.1

Telephone: Abbey 6483/4

Telegrams: Dubelgrip, Sowest, London







*Concrete pumped by pipeline*


## **Heavy Foundations for Cold Reduction Mill at Abbey Works for the Steel Company of Wales Limited**

*Consulting Engineers: W. S. Atkins & Partners*

The Cold Reduction Mill is one of the large steel processing elements in Britain's major steel-works project for the Steel Company of Wales Limited, at Abbey Works, opened on 17th July by The Rt. Hon. Hugh Gaitskell, C.B.E., M.P., Chancellor of the Exchequer.

**LAING**

**Contractors for every class of Building and Civil Engineering work at home and overseas**  
*John Laing and Son Limited, London, Carlisle, Johannesburg, Lusaka. Established in 1848*



*Fixing steel reinforcement*


# POWER BAR BENDERS

## FOR ALL SIZES OF REINFORCING BARS


### STANDARD PRODUCTION MODELS

The ARD. 50 MODEL—as illustrated on right—has a capacity for cold bending Mild Steel Bars up to 2" dia. and incorporates a second Bending Head to give high-rate bending for small diameter bars.

The RAS. 40 MODEL shown below is a single disc machine of exceptional performance. With a capacity for 1½" dia. bars, it bends at highest practical rate—e.g. a full hook takes only 3 seconds bending time.



*Ensure accuracy, economy  
& simplicity of operation*



### INTERESTING FEATURES

Either of the Models illustrated can be supplied motorised or engine driven.

Standard Accessories supplied include all necessary Formers and Bending Pins, a special Backrest for simultaneous bending of a number of small diameter bars, and Accessories for forming right-angle loops in one operation.

Special Safety Device incorporated to prevent damage to mechanism if overloaded.

The desired Bending Angle may be set mathematically, and this is of great assistance in Repetition Bending.

# CEMENT & STEEL LTD.

SECOND AVENUE

CHATHAM

KENT

Telephone: Chatham 45580

Telegrams and Cables: Cembelgi, Chatham



CONSTRUCTED TO THE DESIGN OF  
L. G. MOUCHEL & PARTNERS LTD


**PETER LIND & CO LTD**  
STRATTON HOUSE, STRATTON STREET, PICCADILLY, W.1

TELEPHONE  
GROSVENOR 4601 (10 LINES)

## Take it up with Wickham

WICKHAM Builders' Hoists, all models, include quick fitting Tower Masts which take substantially less time to erect. The Mast sections are designed to butt on to each other and so rabbeted as to be automatically self-aligning. Sections are held together by six bolts only, no fish plates being required. The Power unit is totally enclosed in a steel housing affording complete protection. All Wickham Friction Winches are fitted with self-aligning ball and/or roller bearings, giving longer life and lower maintenance costs. All Wickham Builders' Hoists are fitted with an Automatic platform control which increases the life of the wire bond and prevents crashed platforms.

Leading Contractors on the Festival of Britain sites made extensive use of WICKHAM BUILDERS' HOISTS



*Please write to us for interesting literature and the name of our agent in your area.*

### WICKHAM PRODUCTS

Builders' Hoists (Mobile and Static), Passenger Hoists, Concrete Elevators, Diaphragm Pumps, Power Winches, Portable Winches, Brick Barrows, Safety Gates

★ VISIT US AT THE  
BUILDING EXHIBITION

Nov. 14-28

STAND No. 158-9

TAKE IT UP WITH



# Wickham

WICKHAM  
ENGINEERING CO. LTD.

(Dept. 4) 34 VICTORIA ST., LONDON, S.W.1. Phone: ABBEY 5967-8

Grams: Wicamite Sowest London

# FRANKIPILES

*for major and minor projects*



**Messrs. Fisons Ltd., Immingham**

**Founded on 5,734 Frankipiles**

*Consulting Engineers: Messrs. Maunsell, Posford & Pavry*

**FRANKIPILES CARRY MORE TONS PER PILE**

**THE FRANKI COMPRESSED PILE CO. LTD.**

**30 Victoria Street, London, S.W.1**


*Telephone: ABBey 6006-9.*

*Telegrams: FRANKIPILE, SOWEST, LONDON*

**SOUTH AFRICA: Franki Piling Co. of S.A. (Pty.) Ltd., Durban & Cape Town**

---


# KWIKFORM




**KWIKFORM LTD., WATERLOO RD., BIRMINGHAM 25**

*London Office : 66, Victoria Street, S.W.1.*





Service tunnel constructed with standard formwork.



Foundation works for large Midland Iron Works.

## *...the adaptable concrete formwork*

is designed to meet the widest possible variety of uses: Double or Single Face Work: Columns: Beams: Piers: Battered Retaining Walls, etc., etc.


Patents granted or pending in all principal countries of the world.


Descriptive schedule No. 2599 with terms for hire or purchase will be sent on request.

('KWIKFORM' is the registered trade name of KWIKFORM LTD.)

Formwork erected for construction of Silos.

Construction of houses in "No-Fines" concrete for large Government authorities.





All the concrete on this superstructure was placed with one ACE hoist. Whatever you are building—a power station, factories, offices, flats or houses, your choice of plant is most important. But most important of all is the hoisting equipment, the pacemaker of the job. And that's where we come in. The ACE range of electric, petrol or diesel-driven hoists includes those with hoisting speeds up to 250 ft. per minute, 5/50 cwt. Platform Hoists, Concrete Elevating Plants, Workmen/Goods Hoists, Mobile Platform Hoists, Tunnel Hoists, Shaft Hoists, Transporters, Haulage Winches. Lightweight Portable Winches for hoisting reinforcing bars, etc.

FOR ALL TYPES OF BUILDING CONSTRUCTION

use

**ACE**

hoists

PLATFORM HOISTS WINCHES

**Sale or Hire**



A.C.E. MACHINERY LTD., Porden Road,  
and at Brentford.

Brixton, London, S.W.2  
Telephone : Brixton 3293 (9 lines)

**REINFORCED  
CONCRETE  
ROADS*****Cheapest in the  
long run***

*Architect : R. Lewis Reymish,  
A.R.I.B.A.  
Contractors : Warings (Con-  
tractors), Ltd.*

WITH  
**REINFORCEMENT BY**

Road at Greenwood Avenue,  
Portsmouth, for Mr. John Day,  
South Wymering Farm, Ports-  
mouth, in which McCall's  
Matobar welded fabric rein-  
forcement was used.

**McCALL'S**

**McCALL AND COMPANY (SHEFFIELD) LIMITED**  
TEMPLEBOROUGH, SHEFFIELD • and at LONDON

# GUNITE AND CEMENTATION



Systematic repairs to structures  
based on systematic diagnosis of  
defects.


## WHITLEY MORAN & CO. LTD.

*Specialists in the Repair of Engineering Structures*

5 OLD HALL STREET, LIVERPOOL.

Telephone: Central 7975

# "CAPCO" H. F. VIBRATOR



for compacting mortar cubes  
for Compression Test B.S.  
12/1947, B.S. 915/1947,  
B.S. 146/1947, B.S.  
1370/1947 with automatic  
time control device. The  
vibrator illustrated in the  
B.S. was built in our works.

The "CAPCO" range of con-  
crete testing apparatus also  
includes Cube Moulds; Slump  
Cones; Tensile, Vicat, and Cylind-  
rical Moulds; Tile Abrasion  
Machines; Compacting Factor  
Apparatus.

Full details on request.

## CAPCO (SALES), LTD.

BEACONSFIELD ROAD, LONDON, N.W.10.

Telephone: WILLESDEN 9907-8. Cable: CAPLINKO, LONDON

(Sole Agents for all

"Capco" Products)

# DOUGLAS

RIVERSLEY PARK

NUNEATON



G. ASHTON, A.M.I.C.E., M.I.Mun.E.,  
*Borough Engineer.*

MAGNEL-BLATON EQUIPMENT  
SUPPLIED BY  
STRESSED CONCRETE DESIGN, LTD.

**first prestressed bridge  
in the Midlands  
SPAN 60 ft.**

ROBERT M. DOUGLAS (CONTRACTORS) LTD.

395 GEORGE RD., BIRMINGHAM, 23. AND BRIDGE RD., WAUNARLWYDD, nr. SWANSEA.

# SUPER CEMENT

**'SUBMARINE' BRAND**

THE TANNO-CATALYSED PORTLAND CEMENT

## SAVES TIME

## SAVES TROUBLE

NATURALLY WATERPROOF. CONTAINS NO WATER REPELLENT MATERIAL

### Uses:—

#### For CONCRETE

Provides a CONCRETE of great strength at early dates and impervious to water, oil, etc., without any form of surface coating.

#### For PAVING

Produces a hard wearing PAVING, dustless and proof against penetration by water, etc.

#### For RENDERING

Supplies an impenetrable RENDERING of such adhesive power that a 1" thickness will resist an outside pressure of at least a 20' head of water.

#### For SLURRY (as paint)

Makes a perfectly watertight covering to brick or breeze concrete walls at very small cost, and also provides the best watertight undercoat to coloured finishes.

Technical Information is available to users.

Used in 1914-1918 and still used by:

Air Ministry, War Office, Admiralty, Ministry of Works, Ministry of Supply, etc.

**SUPER CEMENT LTD.,**

29 TAVISTOCK SQUARE, Phone 1  
LONDON, W.C.1 Euston 1808



**PIN YOUR FAITH  
TO THE TESTED  
BRAND.**

THIS LABEL ON  
EVERY BARREL  
CARRIES WITH IT  
FORTY YEARS'  
EXPERIENCE OF  
MANUFACTURE.

**NONE OTHER IS  
"JUST AS GOOD"**


**THE LEEDS OIL & GREASE CO.**

'Phone: 22480.

**LEEDS, 10**

'Grams: "Grease."






W & C  
**FRENCH**  
LTD

Construction of Incinerator House,  
Filter House and Conditioning  
House for the Colne Valley  
Sewerage Board.

Consulting Civil Engineers:  
Sandford, Fawcett and  
Partners

**W. & C. FRENCH, LTD. HEAD OFFICE: 50 EPPING NEW ROAD,  
BUCKHURST HILL, ESSEX**

Telephone: Buckhurst 4444 (13 lines)



An Electrically Driven PC4 Concrete Pump.  
Capacities from 8 to 10 cu. yds. per hour.  
Ranges actually obtained 125 ft. vertical or  
1,500 ft. horizontal.

## CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Pump and Mixing plant can be located where it is most convenient for storing and handling aggregates and cement.
- The concrete is delivered by pipeline just wherever it is required with the minimum of interference with the building operations.
- The speed of the pump governs the whole of the concreting gang.
- Pumpable concrete must of necessity be good concrete.

### THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546.

Telegrams: Pumpcret, Kens, London.



# THORNTONS FOR REINFORCED CONCRETE CONSTRUCTION

The long list of contracts of all kinds and sizes carried out by us in reinforced concrete reflects the very wide experience we have had in this class of work. We undertake contracts in any part of the country, and invite Engineers and Architects to include our name on their lists for future enquiries.

*William*

## THORNTON & SONS LTD



38 WELLINGTON ROAD  
LIVERPOOL 8

# CONCRETE PROOFING Co. LTD.

# GUNITE SPECIALISTS

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request.


100, Victoria Street, Westminster, S.W.1

Telephone: VICTORIA 7877 and 8278

## KEEPING CORROSION AWAY ....


Industrial floors have to be designed to resist the most violently corrosive processes. The illustration shows a five-layer floor of Windsor's materials, scientifically planned to give maximum protection. Windsor's produce a complete range of materials and preparations for proofing concrete and resisting corrosion. Their methods of carefully planned floor laying ensure a liquid-tight and acid-, alkali- or oil-resisting surface which will give years of service without repair.

Details and advice on any problem are gladly given.



## H. WINDSOR & CO. LTD.

748 FULHAM ROAD, S.W.6. Telephone: RENown 6006/7/8  
119 VICTORIA STREET, S.W.1. Telephone: VICToria 9331/2



## When it comes to stress in tension

... nothing can better Isteg Steel (and even nature gets mixed up if she tries). Isteg's combination of twist and cold working long ago established its lead in concrete reinforcement—50% extra on tensile stress—30% less weight—15% off the cost—elimination of hooks or overlengths.

No wonder that Designers whose memories go back to the early days of Isteg keep on specifying it over and over again.

# ISTEG

*for Concrete*



*Reinforcement*

# STEEL

**ISTEG STEEL PRODUCTS LTD. (SALES)**

**43, Upper Grosvenor Street, London, W.1. Tel: Grosvenor 1216**

Isteg is manufactured by Guest Keen & Nettlefolds (Cwmbran) Ltd. Cwmbran

McCall & Co. (Sheffield) Ltd., Templeborough, Sheffield

The United Steel Companies Ltd., Sheffield and Isteg Steel Products Ltd.



By appointment to  
His Majesty The King



Manufacturers of  
Land-Rovers  
The Rover Company Ltd.

## **The 4-wheel drive all-purpose vehicle**

Wherever buildings are going up you need something besides the heavy vehicles, the tractors, the bulldozers—you need the sturdy, speedy, versatile Land-Rover. It's a handy vehicle for the odd jobs, for liaison between site and office; and besides that, its power take-off (providing either belt or shaft drive) makes it a mobile power unit which takes rough ground in its stride and brings power to where it's wanted—right on the spot.

# **LAND- ROVER**

**Britain's most versatile vehicle**


**MADE BY THE ROVER COMPANY LIMITED, SOLIHULL, BIRMINGHAM**

CVS-44



# **CHRISTIANI & NIELSEN LTD**

## **REINFORCED CONCRETE**



**54 VICTORIA STREET,**

**LONDON, S.W.1**

TELEPHONE: VICTORIA 6152

# The latest developments in prestressed concrete production have been adopted by **ANGLIAN** BUILDING PRODUCTS LTD.

Send your enquiries to:

**ANGLIAN BUILDING PRODUCTS LTD.**  
**LENWADE** Tel.: Gt. Witchingham 91 **NORWICH**



GET that new plant into action quickly—speed up the fixings! Machinery and equipment? Bolt it down same day with Rawlbolts. Screw fixings—wiring, lighting, pipes, switchgear and the rest—fix them fast, firm and permanently with Rawlplugs. Rawlplugs are the world's speediest, vibration-proof fixing devices—in brick, cement, concrete and all types of masonry.

**RAWLPLUG**  
WALL PLUGS

**FIXING DEVICES**


WRITE FOR TECHNICAL LITERATURE

*Use Rawlplug Fixing Devices where "speed is the essence of the contract"*

**THE RAWLPLUG COMPANY LIMITED · CROMWELL RD · LONDON · S.W.7**

**ALLAM**

ALL-BRITISH

**HYDRAULIC  
BAR  
CROPPER**

CAPACITY  
ONE 1½ in. dia. MILD STEEL  
or a Multiple of smaller bars

Details of this, the Diesel Model, and also a Comprehensive Range of Concrete Vibrators, sent on request.

**E. P. ALLAM & CO. LTD.**

LONDON: 45 Great Peter Street, S.W.1. Telephone: Abbey 6353 (5 lines)

SCOTLAND: 39 Caledonia St., Glasgow, C.5. Tel.: South 0196. Works: Southend-on-Sea. Tel.: Lastwood 50243

**CONCRETE**

Anderson's Concreting Paper, a bituminised waterproof product, is ideal for road or floor concreting. It prevents the water from draining away from the underside of the concrete, and thus allows a uniform set throughout the thickness. Supplied in rolls 112 yards in length and 36 inches wide. Samples and particulars sent on request.

**ANDERSON'S CONCRETING**


D. ANDERSON & SON LIMITED, STRETFORD, MANCHESTER

Roach Road, Old Ford, London, E.3

**PAPER** *and*  
**FLEXPAND**

EXPANSION JOINTING

# STONE COURT AGGREGATES ★



*General View of Plant at Rickmansworth.*

## ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

High-grade concrete aggregates graded to any specification, and the most punctual delivery service in England, can now be given to all Contractors, Builders, and Municipal Authorities carrying out concrete work and road construction in London and Suburbs and the Home Counties.

Washed all-in Ballast 2 in. down.

$\frac{3}{4}$  in. Washed & Crushed or Un-crushed Shingle.

$\frac{1}{2}$  in. Washed & Crushed or Un-crushed Shingle.

Washed Pit Sand.

Soft Sand.

$\frac{3}{16}$  in. Crushed Grit.



**STONE COURT BALLAST CO. LTD.**  
PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone : Abbey 3456.



---

# Coast Protection Works at Clacton

---

carried out by

# TRENTHAM




**Building and  
Civil Engineering  
Contractors**

## G. PERCY TRENTHAM · LTD

PANGBOURNE, READING.—WOOD LANE, BROMFORD, BIRMINGHAM.—NEW ROAD,  
RAINHAM, ESSEX.—PARK HALL, LONGTON, STOKE-ON-TRENT.—TRINITY HOUSE, EAST  
CANAL WHARF, DOCKS, CARDIFF

---



*Candy Filter House for South-West Suburban Water Company.  
Mr. H. Austin Palmer, Engineer.*

THE BEST WAY to illustrate CONCRETE  
is by HALF-TONE BLOCKS  
OF THE HIGHEST QUALITY

---

*Complete Service of*  
ENGRAVING, TYPESETTING,  
PHOTOGRAPHY,  
ELECTROTYPING and STEREO-  
TYPING and ARTISTS' WORK

---

THE STRAND ENGRAVING COMPANY LIMITED  
8 & 9 ESSEX STREET, STRAND, W.C.2

*Telephones: Temple Bar 6311.*

*Engravers to "Concrete."*





## • GLASCRETE •

Dr. F. F. Curtis, Chief Architect of L.P.T.B. (Western Region), used effectively Glascrete (reinforced concrete and glass) mullion bar windows in his very striking design for Hanger Lane Station, shown above.



**J.A. KING & Co.  
LTD**

151, Queen Victoria St, LONDON, E.C.4

—“there's no need to  
paint GLASCRETE”

Telephone : CENTRAL 5866 (6 lines).

# dustless floors

Concrete dust is fatal to machinery, a severe inconvenience to operatives and a constant menace to production.

“**CCC CASEHARDENING**” process produces a floor which is not only hard—so hard that even by the drastic use of a wire scratch broom no concrete dust can be raised—but is also impervious to water and resistant to the destructive action of oils, grease and soda.

“CCC Casehardening” process is applied only by our trained staff and the result is guaranteed.

“**CCC**” **PREMIX** for Waterproofing, Rapid Hardening,  
and Toughening Concrete

**CONCRETE  
CASEHARDENING  
CO. LTD**



**CRESCENT WHARF • BIRMINGHAM • I**

L.G.B.

# prestressed and precast concrete for building and civil engineering



*A symbol of quality materials, experienced workmanship, expert supervision, and excellent service.*

We specialise in the production of prestressed and precast concrete structural members to standard or special designs, including railway sleepers, and shall be pleased to submit quotations for contracts in most parts of the country.

## H. B. CONCRETE CO LTD

Head Office : East Street, Epsom, Surrey.  
Telephone : Epsom 4041/4042.

Branch Works : Vicarage Road, Egham, Surrey  
Telephone : Egham 3092/3093.

# COLOURS *for* ASPHALT

*Introducing a new range specially prepared for  
ASPHALT by the Manufacturers of the well-known*

## "SHADEACRETE" COLOURS FOR CEMENT

LET US SEND YOU SAMPLES AND PRICES OF

RED • BLUE • YELLOW • GREEN • BROWN

## W. HAWLEY & SON, LTD.

Colour Works, DUFFIELD, Derby

Phone: Duffield 2294/5

COLOUR MAKERS SINCE 1838

Grams: Hawley, Duffield

## CEMENTATION

WILL SEAL WATER LEAKAGES THROUGH CONCRETE, ROCK OR SUB-SOILS, AND WILL STABILIZE SUB-STRATA TO ARREST SETTLEMENT OF STRUCTURES ON FAULTY FOUNDATIONS. ALSO BY THIS PROCESS DETERIORATION OF CONCRETE OR OF MASONRY WORKS CAN BE REMEDIED.

## BORED PILES

CAST *in situ* PILES CAN BE PUT DOWN TO GREAT DEPTH WITH A MINIMUM OF HEADROOM AND VERY LITTLE VIBRATION, WITH DESIGNED BEARING CAPACITY.  
OUR WIDE EXPERIENCE IS AT YOUR DISPOSAL.

## GUNITE

RECONDITIONING DAMAGED AND DEFECTIVE CONCRETE STRUCTURES.  
ENCASING STRUCTURAL STEELWORK.  
LINING TUNNELS, CULVERTS, RESERVOIRS.  
COVERING THE WEARING SURFACES OF CHUTES AND BUNKERS.

**THE CEMENTATION**  
**C.O. LTD.** Telephone Don 54177-8-9 BENTLEY WORKS, DONCASTER.

LONDON OFFICE: 39, VICTORIA STREET, S.W.1  
TELEPHONE: ABBEY 5726-7-8.

## REINFORCED CONCRETE

by

# A. G. MANSELL & CO. LTD

## CIVIL ENGINEERING AND BUILDING CONTRACTORS

BRIDGES - RIVER AND SEA DEFENCE WORKS - WATER TOWERS - BUNKERS

SILOS - INDUSTRIAL BUILDINGS - ROADS - FOUNDATIONS - AND PILING.

78 BUCKINGHAM GATE, LONDON, S.W.1.

TELEPHONE: WHITEHALL 8735-6-7.



setting time of the cement mortar or cement rendering is accelerated with the object of enabling it to be set before the frost can get it. You can continue work under any conditions—and finish it in the shortest possible time.

**IT MAY APPEAR ABSURD !!!**

**but you can**

**concrete below 25° frost**

Important constructional work and housing must continue in frosty weather. Sealocrete Double Strength Premix Solution provides the *maximum safety available*. Even for cement mortar for brickwork and cement renderings, the



**DO NOT RISK A HOLD-UP.**


**STOCK UP NOW.**

by using **SEALOCRETE**  
DOUBLE STRENGTH PREMIX SOLUTION

Sole Manufacturers: **SEALOCRETE PRODUCTS LTD., ATLANTIC WORKS, HYTHE ROAD, LONDON, N.W.10**  
Telephone: LADbroke 0015, 0016, 0017.

Telegrams: Exploiture, Westphone, London

## **DESIGNS AND REINFORCEMENT**



### **TWISTEEL** REINFORCEMENT LIMITED

LONDON: 43 UPPER GROSVENOR STREET, W.1. Tel: Grosvenor 1216. BIRMINGHAM: ALMA STREET, SMETHWICK 40. Tel: Smethwick 1991. MANCHESTER: 7 OXFORD ROAD, MANCHESTER. Tel: Ardwick 1691. GLASGOW: 146 ARGYLE STREET, C.2. Tel: Central 4551.

# GUNITE SPECIALISTS

**W.M. MULCASTER  
& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunite Linings and Renderings  
for new or old structures of every kind in any part  
of the country.

**HASLINGTON**

Telephone: Crews 2265-6.

**CREWE**



## THE "JOHN BULL" CONCRETE BREAKER

NEW "B.A.L." TYPE.

**INCREASED :—**

PENETRATION, RELIABILITY, LIFE.

**REDUCED :—**

VIBRATION, NOISE AND WEAR.

THESE ARE THE SALIENT FEATURES  
OF THE NEW CONCRETE BREAKER

★ ★ ★


**REAVELL & CO., LTD.**

**RANELAGH WORKS, IPSWICH.**

TELEGRAMS: "REAVELL, IPSWICH."

TELEPHONE: 2124





## ***The sure Foundation to all good concrete SISALKRAFT...***

*played an important part in this little bit of hustle.*

18,500 square feet of concrete broken up and all piping removed ; 53,000 linear feet (over 10 miles) of piping relaid on sand bed and then SISALKRAFT, and finally enclosed in 4 inches of concrete, the work being carried out in two stages in 30 days. Such was the schedule for the reconstruction of the Ice Rink Floor at the Harringay Arena. Photograph by kind permission of the Chief Engineer, Harringay Arena Ltd., T. J. Dawes, Esq. Main Contractors : John Morgan (London), Ltd., and Richard Madden, Ltd. Sub-Contractors : G. N. Haden & Sons, Ltd.

Such Structures Suggest

**SISALKRAFT**  
TRADE MARK

The Building Paper

Sole Distributors for British  
Sisalkraft Limited

**J.H. SANKEY & SON, LTD.**

ALDWYCH HOUSE, ALDWYCH, LONDON, W.C.2. Telephone : Holborn 6949. Telegrams : Brickwork, Estrand, London

# COPPER STRIPS


## for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.



### ALEX. J. CHEETHAM LTD.

MORTON STREET • FAILSWORTH • MANCHESTER  
Telephone: FAILSWORTH 1115/6



DELIVERED DIRECT TO ANY  
CONTRACT BY MOTOR LORRY.

Quotations on Application.

Telephone: Paddington 2024 (3 lines).

WASHED  
**BALLAST, SAND, SHINGLE &**  
Crushed Aggregate for Reinforced Concrete.

**WILLIAM BOYER & SONS, LTD.**

*Sand and Ballast Specialists,*

**IRONGATE WHARF,  
PADDINGTON BASIN, W.**

MEMBERS OF B.S. & A.T.A.



# AQUAREP

SEND FOR  
DETAILS

for **100%**  
**WATERPROOF**  
**CONCRETE**

**DAMP-PROOFING LTD.**

DEPTFORD Tel. TIDeway 1486-7 LONDON, E.E.

## **EXPANDED METAL PRODUCTS**

at the

### **BUILDING EXHIBITION**

**Olympia, November 14th to 28th**

**STAND 95**


**ROW E**

### **The Expanded Metal Company, Limited**

Burwood House, Caxton Street, S.W.1.    WHitchall 1736

STRANTON WORKS, W. HARTLEPOOL.    H'pools 2194

ALSO AT: ABERDEEN, BELFAST, BIRMINGHAM, CAMBRIDGE  
CARDIFF, EXETER, GLASGOW, LEEDS, MANCHESTER





**ALPHA CEMENT LTD**

**PORTLAND HOUSE, TOTHILL STREET**

**LONDON, S.W.1.**

*Telephone - Abbey 3456.*



# ACROW

## Adjustable Steel TRENCH STRUTS

AVAILABLE IN 3 SIZES

1' 6"	expanding to 2' 3"
2' 4"	" " 3' 0 1/2"
3' 4"	" " 5' 6"



## Steel TRENCH SHEETING

Reg'd Design No. 850839



In lengths up to 12 feet.

For full details and leaflet, write to :—

**ACROW (ENGINEERS) LTD.**

at one of the following addresses :

{ South Wharf, Paddington, W.2  
22-24, City Road, Bristol, 2  
130, Coventry Drive, Glasgow, E.1  
Lupton Street, Hunslet, Leeds, 10  
West Stanley Street, Manchester, 5

{ Ambassador 3456  
Bristol 24595  
Bridgeton 1041  
Leeds 76514  
Trafford 2965

# MOULD OILS & COMPOUNDS

for every process of  
concrete production

## CONCREAM

This non-staining, smooth and easy working white mould oil can be used with confidence on all classes of in situ and precast concrete work where the use of a white mould oil is recommended.

## VIBRAMOL

This non-staining and non-separating mould oil is made specially for use on steel shuttering and moulds where vibrators are used, and provides a good film which is not readily moved under vibration.

## SPRAYMOL

This grade of mould oil has been specially produced for use with a spray gun. It can be used with great economy on all types of shuttering and moulds, and will not separate under pressure.

## "P.S."

Experience has shown that the production of precast and in situ prestressed concrete needs a special mould compound, and in collaboration with leading prestressed specialists we have produced Grade "P.S." Mould Compound for this class of work.

## "8.A."

This Mould Compound has been specially produced to satisfy the requirements of those engaged in the production of spun concrete products.

**CONCREAM** Regd.  
**VIBRAMOL** Regd.  
**SPRAYMOL** Regd.  
**"P.S." & "8.A."**

PRODUCTS OF THE  
ORIGINAL MAKERS OF  
CONCRETE MOULD OILS

We specialise in the production of mould oils and compounds for concrete work of every kind, from mass concrete work to high-class architectural stone work, and have an unrivalled experience which enables us to give expert advice on all mould oil problems. We have a grade for every purpose, and will be pleased to submit full details, samples, and prices on request.

**RICH<sup>d</sup> HUMBLE & SON, LTD., COLUMBA OIL WORKS, LEEDS, 3**

Telephone : 27155.

ESTABLISHED 1854.

Telegrams : "Columba, Leeds, 3."



# INDUSTRIAL CONSTRUCTION


FACTORIES OFFICES  
FOUNDATIONS

**KENT & SUSSEX  
CONTRACTORS LTD.**

LONDON • SIDCUP • BIRMINGHAM

Government Factory and  
Administrative buildings at  
Chadwell Heath, Essex, by  
Kent & Sussex Contractors


*Associated Company - RUSH & TOMPKINS (S.A.) LTD. Durban Natal.*



# BRC

brings the accuracy of  
the drawing board to the job

*Issued by* **THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD**  
*Specialists in Reinforced Concrete Design & Suppliers of Reinforcement*  
**London, Birmingham, Bristol, Leeds, Leicester, Manchester, Newcastle, Sheffield, Cardiff, Glasgow, Dublin, Belfast**



## STENT PILES

USED FOR THE NEW 150 ft. FACTORY  
EXTENSION FOR FORD MOTOR  
COMPANY LTD., DAGENHAM.

- ★ THEY'RE SAFE
- ★ THEY'RE ECONOMICAL
- ★ LARGE RANGE OF STOCK SIZES

Technical details  
supplied on request to:-


# STENT

## PRECAST CONCRETE LTD.

Sales: 1 Victoria Street, S.W.1. Phone: Whitehall 2573

Works: Dagenham Dock, Essex. Phone: Rainham (Essex) 780

Midland Agent: Fabian J. M. Jackson, M.In.B.E., M.I.P.E., 11 Leicester Road, Loughborough. Phone: Loughborough 3781 and 3543. 56 St. Mary's Road, Manchester, 10. Phone: FAI 2623.




Photographs by kind permission Ford Motor Company Ltd.

## EVODE MELLITOL

Waterproofs AND Improves Concrete, Cement Renderings, Precast Stone. EVODE "MELLITOL" is specially designed to meet your waterproofing problems. Minimises Cracking and Cracking in bulk Concrete. Only 1 lb. "Mellitol" required to 100 lb. of cement—no special mixing. EVODE "MELLITOL" is an established waterproof by PATENT RIGHTS. Severe tests over a period of years in many countries have established its efficiency. Use "MELLITOL" and cut the cost for waterproofing by half.

A new factory for Messrs. Fisons, Ltd., Immingham, near Grimsby. 2,500 cubic yards of reinforced concrete basements of Pump Houses, Pits, etc., Waterproofed with EVODE "MELLITOL"—Patented Concrete Waterproof and Improver. General Contractors: Messrs. A. Monk & Co. Ltd., Civil Engineering and Building Contractors, Padgate, Warrington.



**PATENTED**  
**Mellitol**  
**CEMENT WATERPROOFER**

EVODE LIMITED, GLOVER STREET, STAFFORD. Tel: 1590-1-2. Grams: EVODE

*"The old order changeth yielding place to new"*



BOROUGH OF STOCKTON.

ENGINEER: G. GOWAN, A.M.I.C.E., M.I.Mun.E., A.R.I.C.S.

The reconstruction by Tarslag of the bridge carrying the trunk road A.19 over the Stockton-Darlington line involves dismantling one of the earliest railway bridges in the world. Built by T. Richardson & Sons, Hartlepool Iron Works, in 1851, the passing of this century-old bridge and the erection of the new will not be without interest to engineers and historians all over the world.

# TARSLAG


## LIMITED

CONTRACTORS TO ADMIRALTY, AIR MINISTRY, MINISTRIES OF  
WORKS, SUPPLY, AND OTHER GOVERNMENT DEPARTMENTS,  
MUNICIPALITIES, COUNTY COUNCILS, ETC.

WOLVERHAMPTON · STOCKTON-ON-TEES · ROTHERHAM

# UNDER - WATER CONCRETE PLACING

*With accuracy  
and speed*



The "TREMIE" Concrete Bucket for underwater concrete placing has been successfully used on many important projects, placing concrete in under-water positions as, for example, in dock and harbour construction and repair. The concrete, which is fully protected from swirling water, does not drop

through water and does not displace water when being discharged. There is a complete range of Blaw Knox Concrete Buckets... for every purpose and for big and small jobs.

Write for publication BK-126 illustrating and describing, with data tables, the full range.



## BLAW KNOX CONCRETE BUCKETS

BK 41

THERE'S A BLAW KNOX CONCRETE BUCKET FOR EVERY PURPOSE



"CLAMSHELL GATE" BUCKET

"ROLLER GATE" BUCKET

"TREMIE" UNDER-WATER BUCKET

BATCHING, MIXING AND BULK CEMENT PLANT • CONCRETE MIXERS • MOTOMIXERS • CONCRETE PUMPS  
CONCRETE SPREADERS AND FINISHERS • CONCRETE BUCKETS • STEEL SHUTTERING • ROADFORMS  
DEWATERING PLANT • EXCAVATORS • LAND CLEARING EQUIPMENT • EARTH MOVING EQUIPMENT

BLAW KNOX LTD - 90/94 BROMPTON ROAD, LONDON, S.W.3. Tel. KEN 5151.



# CONCRETE AND CONSTRUCTIONAL ENGINEERING

Volume XLVI. No. 10.

LONDON, OCTOBER, 1951.

## EDITORIAL NOTES

### Proposed Metric System in Great Britain.

ONE of the recommendations of the Committee on Weights and Measures Legislation is that the Imperial system of measurement should be abolished in favour of the metric system, the change being made during a period of about twenty years. As is pointed out in the report of the Committee (published by H.M. Stationery Office, price 3s. 6d.), both systems are legal in Britain at present, although the metric system is not used domestically or extensively in trade other than in the scientific industries. Whereas the metric system is used generally outside the English-speaking countries the Imperial system is used in most English-speaking countries including the United States of America, although some of the standards in the United States differ in magnitude from those bearing the same name in Great Britain. The metric standards in this country differ very slightly from those in use on the Continent, as do also those used in the United States, and the metric standards in Britain and the United States are not identical. There is therefore a lack of harmony between systems that are superficially in agreement, and for this reason the Committee deems it essential for this country, if possible concurrently with the United States of America, to adopt the international metric standards in place of the present Imperial or national metric systems.

In more leisurely days there was less need to simplify methods of measurement, and it was probably not until the present century that the advantages of the metric system were strongly advocated in Great Britain. The British nation was then much more insular than it is to-day, and it was perhaps excusable that a nation of great empire builders and the leaders of industrialisation should expect other nations to adapt their ideas to the British. A view of the last century is expressed by Professor Rankine in one of his rhymes (for Rankine wrote verse as well as works on mechanics). The rhymes are entitled "The Three-foot Rule" and the first two verses are:

When I was bound apprentice, and learned to use my hands,  
Folk never talked of measures that came from foreign lands:  
Now I'm a British workman, too old to go to school;  
So whether the chisel or file I hold, I'll stick to my three-foot rule.

Some talk of millimetres, and some of kilogrammes,  
And some of decilitres, to measure beer and drams;  
But I'm a British workman, too old to go to school,  
So by pounds I'll eat, and by quarts I'll drink, and I'll work by  
my three-foot rule.

Whether Rankine was expressing his own views or those of most of the people of eighty or so years ago we do not know. But aversion to a radical change which will cause much trouble, and particularly if it calls for mental effort and affects everyday life, is a natural reaction which is as evident to-day as it has been throughout history, and we may expect as much opposition to-day as ever before to a proposal to change standards of measurement that have been in use for centuries. English-speaking nations are becoming accustomed to the use of metric measurements in some directions, such as kilowatts in electricity supply, metres in some sports, cubic centimetres in engine capacities, and so on, but these are accepted grudgingly and are meaningless to most people until they have been converted to yards or horsepower, or in the case of kilowatts remain meaningless unless an attempt is made to convert kilowatts to other measurements. It is a waste of time and mental effort to work or think in terms of one system and then to convert the results, and it will often happen that the converted results are impractical. English-speaking users of the metric system should be so familiar with it that it is as natural to think in this system as in the Imperial system. Engineers are not unfamiliar with the metric system because it is used in technical literature on the continent and in physics and chemistry, and it is common for laboratory tests of materials to be expressed in the metric system. The use of decimals certainly eases calculation, and decimals are invariably used in calculations in the Imperial system in structural engineering.

The use of the metric system in Great Britain has now been advocated for many years, and there is no doubt that when they were accustomed to it the wives and workmen, the shopkeepers and manufacturers, would appreciate its simplicity as much as do scientists and mathematicians. The advantages of the system have been pressed often in the past and ignored by successive governments in easier times, for the dislocation that it would cause has always led to the rejection of the proposed change. Indeed the ardent people who advocated the change were often looked upon as fanatics whose proposal was impractical. Such a change, which was considered impractical in the past, may well be thought to be impossible in the foreseeable future. A period when the nation is making armaments against time and when an increase in exports is an immediate and vital necessity is hardly the best time to change our standards of measurement, with the consequent delay and confusion not only while the change is being made but for as long as machines and goods made to the present Imperial standards are in use. In the past such proposals have met with little public approval because of their cost and also because of the desire of any one generation not to cause so much trouble in its own time for the benefit of the next generation. It is likely that this report will be met with the same reservations, and that the difficulties of our times will be sufficient reason for leaving the choice to the next generation, who can pass it on to the succeeding generation if it so desires. The metric system would be a great boon to the country to-day if a previous generation had had the courage to make the change, but it is not likely that the present generation will think it wise to risk disorganisation now for the sake of making life easier for posterity. We may not work so hard or live so well as Rankine's British workman, but British resistance to change is as strong as ever.

## The Ultimate Resistance of Prestressed Concrete Beams.

By P. W. ABELES, D.Sc. (Vienna).

THE factor of safety of a beam is the ratio of the ultimate moment of resistance to the moment of resistance at working load. For a prestressed concrete beam, the factor of safety cannot be derived from the resultant stresses at working load because these stresses are composed of the effective prestress (compressive or tensile) and the stresses due to the working load, and are based on a rectilinear distribution in an elastic homogeneous material.

At failure, however, the concrete beam is cracked and in a plastic state and the condition of stress is entirely different. Consequently it is necessary to investigate separately the stresses at working load and at failure. In this article the ultimate resistance to bending is considered, and it is intended to deal with the elastic state in a later article. The terms "under reinforced" and "over reinforced," which are commonly applied to beams in which failure is due primarily to failure of the steel and concrete respectively, are used with these meanings in the following.

The magnitude of the factor of safety required depends on whether the resistance of the steel or concrete is considered. A factor of safety of two should be sufficient for the tensile resistance, but 2.5 to 3 is required for compressive resistance because the strength of the concrete is not known accurately and may vary greatly. It may be better to use different load factors for the dead and live loads, for example, with regard to the steel 1.5 for the dead load and 2.5 for the live load and similarly increased values with regard to the concrete. The same value ( $FS = 2$ ) can be used for the steel and concrete if the compressive strength of the concrete is reduced to the lowest probable value by including a reduction factor of  $\frac{2}{2.5} (= 0.8)$  or  $\frac{2}{3} (= 0.67)$ .

The two common methods of prestressing, which must be considered separately, are (1) Pre-tensioning, that is when the wires are stretched before the concrete is placed and released after the concrete has attained sufficient strength, and are bonded to the concrete, and (2) Post-tensioning, that is when the wires or bars are stretched when the hardened concrete can resist the compression applied by the anchors at each end, the wires not being bonded to the concrete at the time of stretching. Professor R. H. Evans\* then was probably the first to describe the difference in behaviour of beams with bonded and non-bonded wires. Beams with pretensioned wires and beams in which post-tensioned wires are efficiently bonded to the concrete by grouting are considered as beams with bonded wires. Beams with post-tensioned wires without grouting or with inefficient grouting are considered as beams with non-bonded wires or bars.

With bonded wires, failure occurs as in an ordinary reinforced concrete beam. The magnitude of the prestress in an under-reinforced beam has little influence on the ultimate load. High-strength steel wire has generally no distinct yield point and, if the percentage of steel is low and the wires are small, a stress

\* "Relative Merits of Wire and Bar Reinforcement in Prestressed Concrete Beams." *Journal of the Institution of Civil Engineers*, February, 1942.

that by calculation is equal to or exceeds the tensile strength will be reached because the greatest extension of the wires occurs only at the cracks, that is only for a fraction of the length of the beam. At failure, the neutral axis rises considerably, due to either a tensile fracture of the wires or excessive elongation of the steel, followed by crushing of the concrete. The minimum load that will cause failure can be determined, and considerable deflection and cracking indicate that failure is imminent.<sup>1</sup> Failure of an over-reinforced beam with bonded wires is due to crushing of the concrete without substantial elongation of the wires, and occurs suddenly when the deflection is relatively small and cracking does not indicate immediate collapse. The magnitude of the load that causes failure is doubtful and depends on the strength and plasticity of the concrete and shape. The crushing strength is about equal to the prism strength, which may be from 60 per cent. to 90 per cent. of the cube strength.

In a beam non-bonded post-tensioned wires or bars act as an independent tie, freely extending between the end anchors, and do not fracture. The calculated stress at failure is consequently never so great as the tensile strength, since extension of the wires exists throughout the length of the beam. Failure of the beam is always a result of the crushing of the concrete as a consequence of the great deflection, the amount of which depends on the initial prestress, the stress-strain relationship of the wire, the strength and plasticity of the concrete, and the shape of the moment diagram. The percentage of steel, which has a particular influence with bonded wires and distinguishes under-reinforced and over-reinforced beams, is of minor importance in a beam with non-bonded wires, and the size of the wire or bar is not restricted, but the elastic limit should be high to avoid excessive extension.

#### Design Formulæ for Beams with Bonded Wires.

In view of the difference in behaviour of beams with bonded or non-bonded wires, it is impracticable to devise a formula for the design of all beams, but it is possible to adopt the same principal formulæ and use different values of the maximum stress in the wires at failure. In this journal for June, 1946, the writer gave a formula based on the condition at ultimate load for the calculation of the total area of reinforcement ( $A_t$ ) composed of stretched wires ( $A_{ts}$ ) and unstretched bonded wires ( $A_{tu}$ ). The formula can also be stated as

$$A_t = A_{ts} + A_{tu} = \frac{M_w \cdot FS}{a_p t_{max}} \quad (1)$$

in which  $M_w$  is the bending moment due to the design load,  $FS$  the factor of safety, and  $t_{max}$  the tensile stress in the steel at failure. The lever arm  $a_p$  is that of a cracked section assuming a rectangular distribution (plastic) of stress  $c_p$ , that is the prism strength. Tests show that this simple approximation<sup>2</sup> is reliable for under-reinforced beams, and that in stretched and unstretched wires up to 0.2 in. diameter, if the bond is efficient,  $t_{max}$  is equal to the tensile strength of the wire ( $t_{ult}$ ). Otherwise, with bonded unstretched reinforcement,  $t_{max}$  is 85 per cent. to 100 per cent. of  $t_{ult}$ , the proportion depending on the efficiency of the bond (which depends on the size and surface of the wire), the stress-strain characteristics of the steel, and the strength of the concrete. For post-tensioned grouted wires  $t_{max}$  may be between 75 per cent. and 100 per cent. of  $t_{ult}$ , depending



in which  $K_u$  varies from 0.85 to unity. In a balanced design,  $C_{max.} = T_{ult.}$  if the factors of safety for the steel and concrete are equal.

In a beam with efficiently-grouted post-tensioned wires, the ultimate resistance of the wires is generally  $(A_{ts}K_g + A_{tu}K_u)t_{ult.}$ , in which  $K_g$  is from 0.7 to unity depending on the efficiency of the grout. All considerations of bonded conditions relate only to wires, since test data of bars are not available.

Table I gives values of the factors  $K_2 \left( = \frac{n_p}{d} \right)$ ,  $K_3 \left( = \frac{a_p}{d} \right)$ , and  $K_4 \left( = \frac{M_{ult.}}{M_{max.}} \right)$  for various values of  $K_1 \left( = \frac{T_{ult.}}{C_{max.}} \right)$ . If  $T_{ult.}$  is less than  $C_{max.}$  the beam is under-reinforced, but if greater the beam is over-reinforced and  $M_{ult.} = M_{max.}$  for which formula (2) applies. Fig. 2 shows the value of  $\frac{M}{bd^2c_u}$  plotted against  $K_1$ , which can also be considered as the ratio of  $p \left( = \frac{100A_t}{bd} \right)$  to  $\bar{p}$ , which, in accordance with the assumption in Fig. 1 for balanced design, is

$$\bar{p} = \frac{100\bar{A}_t}{bd} = \frac{30c_u}{t_{max.}} \quad (4)$$

Curves are given for the ultimate and permissible loads. Thus the permissible bending moment for safe balanced design is  $0.09bd^2c_u$  and  $0.075bd^2c_u$  if  $FS$  is 2.5 and 3 respectively, the corresponding values of  $K_1$  or  $\frac{p}{\bar{p}}$  being 0.735 and 0.586 as indicated in Fig. 2. These values are obtained from  $K_4 = \frac{4K_1K_3}{3}$ , on which Table I is based. Since  $K_2 = \frac{K_1}{2}$ ,  $K_3 = 1 - \frac{K_1}{4}$ . Therefore  $K_4 = \frac{4K_1}{3} \left( 1 - \frac{K_1}{4} \right)$ .

TABLE I.—COEFFICIENTS FOR ULTIMATE MOMENT OF RESISTANCE OF RECTANGULAR BEAMS.

$K_1 = \frac{T_{ult.}}{C_{max.}}$	$K_2 = \frac{n_p}{d}$	$K_3 = \frac{a_p}{d}$	$K_4 = \frac{M_{ult.}}{M_{max.}}$	Notes	
0.1	0.05	0.975	0.130	—	Under-reinforced beams
0.2	0.10	0.95	0.253	—	
0.3	0.15	0.925	0.370	—	
0.4	0.20	0.90	0.480	—	
0.5	0.25	0.875	0.584	—	
0.6	0.30	0.85	0.680	—	
0.667	0.333	0.833	0.740	Limit : $FS_{concrete} = 3$	
0.7	0.35	0.825	0.770	—	
0.8	0.40	0.80	0.853	Limit : $FS_{concrete} = 2.5$	
0.9	0.45	0.775	0.930	—	
1.0	0.50	0.75	1.00	Balanced design : $FS_{concrete} = 2$	



The percentage of steel for balanced design is reduced to

$$0.735\bar{p} = \frac{22.05c_u}{t_{max.}}$$

for  $FS = 2.5$ , and to  $0.586\bar{p} = \frac{17.58c_u}{t_{max.}}$  for  $FS = 3$ . If  $c_u = 7000$  lb. per square inch, and  $t_{max.} = t_{ult.} = 224,000$  lb. per square inch, from (4)  $\bar{p}$  is 0.94 per cent. for actual balanced design, but is reduced to 0.69 and 0.55 per cent. for safe permissible balanced designs with  $FS$  equal to 2.5 and 3 respectively.

In the foregoing the magnitude of the initial prestress is disregarded, which is justified for a beam for which  $K_1$  is small (even if the prestress is very small), or if the value of  $K_1$  approaches unity provided that the initial prestress is from  $0.6t_{ult.}$  to  $0.7t_{ult.}$ . There is a possibility that, for values of  $K_1$  approaching unity, lower values of  $M_{max.}$  apply if the prestress is below  $0.6t_{ult.}$ . At present, although




Fig. 4.

there are no data available regarding this matter, the possibility of such a reduction of the maximum resistance if there is a small prestress should not be overlooked.

### I-Beams with Bonded Wires.

It appears to be permissible in an under-reinforced I-beam (Fig. 4) to assume the stress in a shallow top flange to be greater than  $0.6c_u$ , depending on the actual prism strength, even up to, say,  $0.9c_u$ . It may be justifiable to use a greater stress than  $0.6c_u$ , say,  $0.75c_u$ , if exact data are not available. Table I can be applied to I-beams by calculating a nominal maximum value of  $M_{max.}$  from  $0.375B_2d_{av}^2c_p$ ,

while the actual maximum value for depth  $d'_f$  and lever arm  $d_{av.} - \frac{d'_f}{2}$  is given by

$$M_{max.} = B_2d'_f\left(d_{av.} - \frac{d'_f}{2}\right)c_p.$$

If  $c_p = 0.75c_u$ , the nominal value is  $0.28B_2d_{av.}^2c_u$ .

### Beams with Non-bonded Wires or Bars.

Since the greatest stress in the steel at failure is governed by the greatest extension, it mainly depends on the stress  $p_t$  in the steel at the time when the force is applied to the concrete. In beams with post-tensioned wires or bars, the force is transmitted from the wires or bars to the concrete by the anchors,

and not by bond as is the case with pre-tensioned wires or bars. If  $p_t$  is  $0.65t_{ult.}$  a safe value for  $t_{max.}$  is  $0.75t_{ult.}$  and  $T_{ult.}$  is then  $0.75A_t t_{ult.}$ . If  $p_t$  is less than  $0.65t_{ult.}$  smaller values of  $t_{max.}$  should be assumed. The governing factor is the maximum elongation  $\Delta l$  possible, and  $t_{max.} - p_t$  should in each case correspond to the same strain (Fig. 3). However, a simple and safe approximation is that  $t_{max.} = p_t + 0.1t_{ult.}$ , which gives a more unfavourable condition for low values of  $p_t$  but shows that it is not advisable for the initial prestress  $p_t$  to be too small. Generally, therefore, the tensile resistance is given by

$$T_{ult.} = A_{ts}(p_t + 0.1t_{ult.}) + K_u A_{ts} t_{ult.} \quad (5)$$

It is seen that unstretched well-bonded wire is much more efficient as regards the ultimate stress than non-bonded wires or bars with a small prestress. Table I can be used for the design of beams with non-bonded wires, but the reduced value of  $T_{ult.}$  must be used.

### Examples.

RECTANGULAR BEAMS.—Assume  $d = 12$  in.,  $b = 6$  in.,  $c_u = 9000$  lb. per square inch, and  $t_{ult.} = 100$  tons per square inch. All wires 0.2 in. diameter. Then  $c_p = 0.6c_u = 5400$  lb. per square inch.

$$C_{max.} = 6 \times 6 \times 5400 = 194,000 \text{ lb.} = 86.8 \text{ tons.}$$

$$M_{max.} = 0.225 \times 6 \times 12^2 \times 9000 = 1,750,000 \text{ in.-lb.}$$

(a).—Provide ten wires pre-tensioned ( $A_t = 0.314$  sq. in.).

$$T_{ult.} = 31.4 \text{ tons. } K_1 = \frac{T_{ult.}}{C_{max.}} = 0.362. \text{ From Table I,}$$

$$M_{ult.} = T_{ult.}(K_3 d) = 31.4 \times 2240 \times 0.91 \times 12 = 768,000 \text{ in.-lb.,}$$

$$\text{or } M_{ult.} = K_4 M_{max.} = 0.438 \times 1,750,000 = 766,500 \text{ in.-lb.;}$$

$$\text{or directly, } a = 12 - \frac{31.4 \times 2240}{2 \times 6 \times 5400} = 10.91 \text{ in., and}$$

$$M_{ult.} = 31.4 \times 2240 \times 10.91 = 767,400 \text{ in.-lb.}$$

(b).—Provide twelve wires pre-tensioned ( $A_{ts} = 0.377$  sq. in.), and eight wires not tensioned ( $A_{tu} = 0.251$  sq. in.). Assume  $K_u = 0.95$ .

$$T_{ult.} = (0.377 \times 100) + (0.251 \times 100 \times 0.95) = 61.5 \text{ tons.}$$

$$K_1 = \frac{61.5}{86.8} = 0.708; \quad M_{ult.} = 0.777 \times 1,750,000 = 1,360,000 \text{ in.-lb.}$$

(c).—Provide 48 wires pre-tensioned ( $A_t = 1.507$  sq. in.).

$T_{ult.} = 1.507 \times 100 = 150.7$  tons, which is greater than  $C_{max.}$ . Therefore the beam is over-reinforced and  $M_{ult.} = M_{max.} = 1,750,000$  in.-lb.

(d).—Provide 24 wires post-tensioned and not bonded ( $A_t = 0.754$  sq. in.). Assume  $p_t = 68$  tons per square inch and  $K_g = 0.75$ .

$$T_{ult.} = 0.754 \times 0.75 \times 100 = 56.5 \text{ tons.}$$

$$K_1 = \frac{56.5}{86.8} = 0.651.$$

$$M_{ult.} = 0.727 \times 1,750,000 = 1,272,000 \text{ in.-lb.}$$

(e).—As (d) but  $p_t = 40$  tons per square inch.  $t_{max.} = 40 + (0.1 \times 100) = 50$  tons per square inch.

$$T_{ult.} = 0.754 \times 50 = 37.7 \text{ tons.}$$

$$K_1 = \frac{37.7}{86.8} = 0.435.$$

$$M_{ult.} = 0.516 \times 1,750,000 = 903,000 \text{ in.-lb.}$$

I-BEAM (Fig. 4).—Assume that  $d = d_{av.} = 12$  in.,  $B_2 = 8$  in.,  $d_f' = 4$  in.,  $b = 2$  in.,  $c_u = 8000$  lb. per square inch,  $c_p = 6000$  lb. per square inch,

$$t_{max.} = t_{ult.} = 120 \text{ tons per square inch,}$$

$K_u = 1$  for unstretched wires because good bond is assured, and  $FS = 2$  for steel and 2.5 for concrete. Determine the cross-sectional area of wires required.

(a) To resist the maximum permissible bending moment.

$$C_{ult.} = B_2 d_f' c_p = 8 \times 4 \times 6000 = 192,000 \text{ lb.; } a_{min.} = d - \frac{d_f'}{2} = 10 \text{ in.}$$

Permissible bending moment  $M_w$  due to the working load

$$= \frac{C_{max.} a_{min.}}{(FS_{concrete})} = \frac{192,000 \times 10}{2.5} = 768,000 \text{ in.-lb.}$$

$$A_t = A_{ts} + A_{tu} = \frac{(FS_{steel})M_w}{a_{min.} t_{max.}} = \frac{2 \times 768,000}{10 \times 120 \times 2240} = 0.57 \text{ sq. in.}$$

(b) To resist bending moment  $M_w$  of 500,000 in.-lb.

A nominal  $M_{max.}$  for a rectangle must be computed. Since  $c_p = 0.6c_u = 6000$  lb. per square inch, the nominal value of  $c_u$  is 10,000 lb. per square inch, and

$$M_{max.} = 0.225 \times 8 \times 12^2 \times 10,000 = 2,590,000 \text{ in.-lb.}$$

$$K_1 = \frac{T_{ult.}}{C_{max.}} = \frac{(FS_{steel})M_w}{M_{max.}} = \frac{2 \times 500,000}{2,590,000} = 0.386; \text{ the corresponding}$$

value of  $K_3$ , from Table I, is 0.903. Therefore

$$A_t = A_{ts} + A_{tu} = \frac{(FS_{steel})M_w}{K_3 d t_{max.}} = \frac{2 \times 500,000}{0.903 \times 12 \times 120 \times 2240} = 0.333 \text{ sq. in.}$$

### Tests.

Tests made by the writer in association with Mr. C. H. Hockley at the Brixton School of Building show that these formulæ give safe results. In addition to




Fig. 5.

TABLE II.—COMPARISON OF CALCULATED RESULTS WITH TESTS.

Beam No. . . . .		1	2	3	
No. of stretched wires	Total . . . . .	2	2	2	
	Bonded . . . . .	—	2	2	
	Unbonded . . . . .	2	—	—	
No. of unstretched wires . .		—	—	2	
$A_t = A_{ts} + A_{tu}$ . . . . .		0.0168	0.0168	0.0336	sq. in.
$d_{av}$ . . . . .		3.75	3.75	3.375	in.
Initial stretching force $P_i$ . .		1900	1900	2100	lb.
Initial tensile stress $p_i$ . . .		113,000	113,000	125,000	lb. per square inch
Cube strength $c_u$ of concrete at time of test . . . . .		6800	6800	8040	lb. per square inch
Failure load $W_{ult}$ . . . . .		0.525	0.95	1.40	ton
Maximum deflection . . . . .		0.8	1.3	1.0	in.
Number of cracks in beam . .		1	5	8	
$M_{ult} = 10W_{ult} + M_s^*$ . . . .		5.42	9.67	14.17	in.-tons ( $M_s = 0.17$ )
$M_{ult}$	By test . . . . .	12,150	21,650	31,750	in.-lb.
	By calculation . . . . .	8,660	17,850	29,500	in.-lb.
$\frac{M_{ult. \text{ by test}}}{M_{ult. \text{ by calculation}}}$		1.40	1.21	1.075	

\*  $M_s$  is the bending moment due to the weight of the beam.

some beams tested in 1949 and 1950,\* three beams (Fig. 5) were tested in 1951. The beams were prestressed by No. 12 gauge wires (0.0084 sq. in.) having a tensile strength of 138 tons per square inch. (The stress in some test pieces of wire which broke at the grips was less.) Comparison of the calculated and actual ultimate moments of resistance are given in Table II by permission of Mr. D. A. G. Reid, the Principal of the School. The calculations are as follows.

BEAM No. 1.— $C_{max.} = 0.3 \times 3.75 \times 2 \times 6800 = 15,300$  lb.  $M_{max.} = 0.225 \times 2 \times 3.75^2 \times 6800 = 43,100$  in.-lb.  $p_t = \frac{1900}{0.0168} = 113,000$  lb. per square inch.

An arbitrary safe value of  $t_{max.}$  is  $p_t + 0.1t_{ult.} = 113,000 + (0.1 \times 310,000) = 144,000$  lb. per square inch.  $T_{ult.} = 0.0168 \times 144,000 = 2420$  lb.  $K_1 = \frac{T_{ult.}}{C_{max.}} = \frac{2420}{15,300} = 0.158$ ; from Table I,  $K_4 = 0.201$ ; hence  $M_{ult.} = 0.201 \times 43,100 = 8660$  in.-lb.

BEAM No. 2.— $C_{max.}$  and  $M_{max.}$  are as for beam No. 1;  $t_{max.} = 310,000$  lb.

\* "Small Scale Demonstration Tests on Prestressed Concrete Beams." By P. W. Abeles and C. H. Hockley. "The Structural Engineer", June, 1950.

per square inch, and  $T_{ult.} = 0.0168 \times 310,000 = 5210$  lb.,  $K_1 = \frac{5210}{15,300} = 0.34$ , and  $K_4 = 0.414$ . Hence  $M_{ult.} = 0.414 \times 43,100 = 17,850$  in.-lb.

BEAM No. 3.— $C_{max.} = 0.3 \times 3.375 \times 2 \times 8040 = 16,250$  lb.  $M_{max.} = 0.225 \times 3.375^2 \times 2 \times 8040 = 41,100$  in.-lb.  $T_{ult.} = 2 \times 5210 = 10,420$  lb., which is twice the value for beam No. 2 corresponding to  $K_u = 1$ .  $K_1 = \frac{10,420}{16,250} = 0.641$ ;  $K_4 = 0.717$ . Hence  $M_{ult.} = 0.717 \times 41,100 = 29,500$  in.-lb.

This article is in general agreement with the "First Report on Prestressed Concrete" published by the Institution of Structural Engineers, September, 1951.

#### Notes.

(1)—There are two exceptions when failure of an under-reinforced beam may occur suddenly, namely, when the precompression is so great that cracking and failure occur simultaneously, that is the beam is over-prestressed, and when the percentage of steel is so small that after cracking of the concrete the wires are incapable of resisting the tensile force. Consequently the percentage should not be less than 0.15 (related to the width at the bottom) if the wire has a tensile strength of 100 tons per square inch, or  $\frac{15}{t_{ult.}}$  if the strength of the wire is  $t_{ult.}$  tons per square inch.

(2)—There are several methods of design such as those, based on the ultimate strain of the concrete in compression and of the steel in tension, of Professor A. L. L. Baker (Journal of Institution of Civil Engineers, February, 1951) and Mr. J. W. H. King (this journal, September, 1950). The latter method is based on the average elongation measured over one or more cracks. If the steel is bonded to the concrete the average strain does not represent the maximum strain on which failure depends and which occurs in the cracks. In the writer's view it is possible to obtain a relationship between the average and maximum steel strains only for beams of the same cross section and made with the same concrete, and having wires of the same quality, size, and strength. Extensive research would be required to obtain reliable design data. Consequently, only approximations are possible at present, and the simplest solution seems to be preferable.

#### Proposed Concrete Dam in Ceylon.

TENDERS are invited for hydro-electric works at Watawala, Ceylon, including the construction of a mass concrete dam 730 ft. long and 130 ft. high. Further information may be had from the Crown Agents for the Colonies, 4 Millbank, London, S.W.1, the reference number CRE(IB)71489/51 should be quoted.

## Plastic Hinges.

PROFESSOR A. L. L. BAKER (Professor of Concrete Technology at the Imperial College of Science and Technology) writes:

I have read the Editorial Note of your September number with great interest, and would like to contribute a few comments.

Recent research has shown that in beams the rotation of plastic hinges is mainly due to yield of the reinforcement, which is accompanied by a rise of the neutral axis. The rotation afforded by the plasticity of the concrete is small in comparison. Provided that the neutral axis rises sufficiently before the concrete in the compressive zone fails by crushing, adequate rotation can be provided and the difficulties of calculation that you suggest exist in connection with tee-beams thus disappear.

Columns and members of frames subjected to compression only, particularly those in which the eccentricity of the direct force is small, present greater difficulty because rotation of plastic hinges which may form depends on the difference of strain which can develop in the concrete across the section. Tests

are now proceeding to try to find ways of adjusting reinforcement and binding locally which will ensure that sufficient difference of strain can develop before failure takes place.

Reinforced concrete frames, it is anticipated, may therefore have an advantage over structural steel in the application of the plastic theory. The positions of plastic hinges will be assumed at suitable points and reinforcement adjusted locally until the elastic flexural stiffness of the members and the available plastic rotation of the hinges are within the required limits. Also it is not difficult to calculate approximately by moment distribution, applied to the results obtained by the plastic theory, the stresses under working load to ensure that cracking will not occur.

There should be no narrow or rigid adherence to either the elastic or the plastic theory. Each should be used with intelligent discrimination when it is appropriate. Further research, it is anticipated, will extend the useful application of the plastic theory by simplifying calculations and more precisely evaluating factors of safety.

## Book Review.

**"Rüstungsbau."** By H. Kirchner and Adolf Müllenhof Lübeck. 2 vols. (Berlin: Wilhelm Ernst & Sohn. 1951. Prices: Vol. I, 21.50 D.M.; Vol. II, 16.50 D.M.)

VOLUME I deals with the principles of calculation and design of staging for bridges. Data on the strength of materials and permissible stresses are given, and constructional details are treated in great detail. Stagings for use where clearances are required to maintain traffic on railways and waterways are discussed in detail with many examples. Staging for fixed steel-girder bridges with horizontal and curved booms, for arch and suspension bridges and for the movement of bridges are dealt with. The use of boats for floating bridges into position is referred to, and methods of lifting bridges are discussed.

Volume II describes centering for concrete arches, separate sections dealing with the use of struts and braces, fan-shaped arrangements of timbering, staging supported on posts, trestles, and timber

piles, and combinations of staging and trusses. Methods of erection and removal in each case are considered, and useful information is given on auxiliary staging required for the transport of building materials and the movement of cranes.

Clear illustrations with details and sizes of the members are a feature of the book.

### Publication Received.

**"First Report on Prestressed Concrete."** The Institution of Structural Engineers. 32 pages. 1951. Price 3s. 6d.

### Airfield near Bedford.

An airfield is to be built at the National Aeronautical Establishment near Bedford at a cost of more than £3,000,000. The contract has been awarded to Messrs. John Laing & Son, Ltd.



# Construction of a Large Jetty on Southampton Water.

## PILE HAMMERS OF 4 TONS AND 8½ TONS.

THE construction of the jetty for the new refinery for the Esso Petroleum Co., Ltd., at Fawley on Southampton Water, required the use of unusual equipment, some of which was floating. The design of the jetty was described in this jour-

The approach is carried on 16-in. by 14-in. precast piles. The extensive temporary works included a casting yard and an embankment and trestle carrying a railway from the yard to works off the land, where the caissons were constructed.




Fig. 1.—Plan of Casting Yard.

nal for September, 1951. Briefly, the main structures comprise a pierhead trestle 2470 ft. long in continuation of which there are two mooring dolphins at each end connected to the pierhead trestle by catwalks. The distance between centres of the outer mooring dolphins is 3200 ft. On the seaward side of the pierhead trestle are four berthing islands, and on the landward side a trestle connecting to a pump-house area and an approach 1900 ft. long. The pierhead trestle, berthing islands, and connecting trestle are built with 32 in. cylindrical hollow precast reinforced concrete piles, reinforced concrete caissons of 36 ft. and 40 ft. diameter, and precast frames.

### Casting Yard.

The casting yard (Fig. 1) was on a levelled site about 1000 yd. from high-water line and adjacent to a road and railway, a standard-gauge siding from which ran into the yard. Timber and other stores were unloaded on one side of the siding and reinforcement on the other side where there was a siding from the site railway. There were four principal casting areas. One of these was 41 ft. wide and had nine parallel beds about 600 ft. long for the cylindrical piles. An area of the same width had twenty parallel beds about 230 ft. long for the rectangular piles, and another about




Fig. 2.—Arrangement of Temporary Works.

350 ft. long was used for casting the large frames. A smaller area was used for casting struts, beams, and gangways. At one part of the yard, small concrete blocks to be used as distance-pieces for spacing reinforcement were cast, two men being employed solely on this work.

The paving of the casting yard was generally a 6-in. concrete slab. Each of the two lines of main beds was spanned by two 48-ft. travelling gantries carrying 10-tons chain-blocks. There were also two 4-tons mobile cranes. A boiler supplied steam for heating the castings in

trestle, the railway was a double track (Fig. 2) carried on steel beams supported on timber-pile trestles at 20 ft. centres. The tracks, between which there was a 6-ft. gangway, were at 15 ft. centres. The piles, of which there were 420, were 12 in. square and 70 ft. long, and were driven by a 2-tons drop-hammer in a cantilever frame with a leader for each row of piles.

Near the site of the jetty, a branch led to a pontoon from which aggregates and cement were loaded on to barges carrying mixing plants. A branch also led to a




Fig. 3.—Rectangular Piles on Site Railway.

winter, and a 115-cu. ft. compressor supplied air for cleaning out the moulds. Power-driven machines were used for bending reinforcement, and equipment was provided for butt welding the long bars in the piles. The quantity of concrete cast daily when the yard was fully in operation was about 50 cu. yd.

#### The Site Railway.

The site railway had a gauge of 3 ft. and comprised about 2 miles of track. It extended as a single track, on an embankment alongside the pipe-line across the low-lying ground, from various sidings in the casting-yard to the shore. From the shore to the terminus behind the pierhead


berth 100 ft. by 42 ft. where the cylindrical piles and precast frames were loaded on to barges, which were towed to the driving positions. There were two fixed gantries spanning the track and barge-berth, each carrying a 10-tons chain-block which enabled the concrete members to be picked up at two points and placed on the barge (Fig. 2). Another branch proceeded to the berths where the caissons were cast.

Materials were transported on the railway in  $1\frac{1}{2}$ -cu. yd. side-tipping skips, of which there were twenty-four. Long concrete and steel piles, frames, and similar long pieces were transported on double-bogies. Four 5-tons and one 3-tons Diesel locomotives were used.

### Concrete Plant.

Much of the concrete was supplied from a mixing plant operated by Messrs. Foster Wheeler, Ltd., about a mile from the new refinery and casting yard. At this plant, which was described in this journal for May, 1951, air-entrained concrete was

The two floating mixing plants previously mentioned were each on a barge carrying fine aggregate, coarse aggregate of two sizes, and cement. At the forward end was a mixer and a crane for handling skips of concrete. The materials were measured in boxes. The smaller floating plant, seen on the left in *Fig. 4*, was used



**Fig. 4.—Driving Rectangular Piles.**

produced and was delivered in 3-cu. yd. lorries either to the casting yard or to the seaward end of the railway embankment whence it was conveyed to the jetty in skips on the railway. During night shifts, and at other times when supplies from this plant were not available, concrete without an air-entraining chemical was mixed on the site. There was a stand-by mixer in the casting yard, and mixing plants at the end of the embankment and on the staging by the caisson berth.

for the concrete placed in the joints between the precast members of the pier-head trestle and berthing islands. The larger plant, which had a 14/10 mixer, was used for concreting the decks of these structures, the concrete being deposited through a short length of chute.

### Rectangular Piles.

The 16-in. by 14-in. rectangular piles, of which there are 637 in the approach, are from 55 ft. to 85 ft. long and weigh up



**Fig. 5.—Driving Rectangular Piles with 4-tons Hammer.**

to 9 tons each. Under each ordinary transverse frame there are three vertical piles and two piles inclined at a batter of 1 : 3, or in some cases four vertical piles. The frames are at 20 ft. centres and the distance between the outer piles is 47 ft.




Fig. 6.—Cylindrical Piles on Concrete Mould-base.



Fig. 7.—Transporting a Cylindrical Pile.

The piles were brought from the casting yard to the site on the temporary railway (Fig. 3) parallel to the approach, and were lifted by a three-point suspension by the pile-driver acting as a crane.

The vertical piles were driven by a cantilevered frame (Fig. 4), the undercarriage of which comprised two transverse steel beams 14 ft. apart carried on two bogies running on longitudinal mono-rails 47 ft. apart. The frame was carried on steel cantilevers supported on and rotated about a four-wheel bogie on rails on the transverse beams. The longitudinal beams were supported on a lower tier of transverse beams bearing on piles already driven, the heads of which were cut off and protected by a steel cap. The length of the cantilever was such that piles were driven 20 ft. ahead of those supporting the undercarriage. The set to which the piles were driven was 12 in. for 120 blows from a 4-tons single-acting steam hammer (Fig. 5) falling 18 in. The points of the piles, which are driven to gravel overlying clay, are wedge-shape and are protected by steel plates. The inclined piles were driven from an ordinary pile-frame travelling on a grid laid on the vertical piles.

#### Cylindrical Piles.

There are 503 32-in. diameter precast hollow piles 75 ft. to 90 ft. long weighing up to 18 tons each in the trestles and berthing islands. The thickness of the





Fig. 8.—Berth for Loading Precast Members on to Barges.





**Fig. 9.—Driving Cylindrical Piles with 8½-ton Hammer.**

wall of the pile is 5¼ in. The moulds were in five separate parts. The lowest part was a segmental concrete cradle, seen in *Fig. 6*, cast on the bed of the casting yard for the full length of the pile. The cradles, of which there were 38, formed the bottom quadrant. The two side quadrants were

shaped by shutters in short lengths made of stout timber templates with steel plate attached. The upper quadrants were shaped by two steel shutters which hinged about the shutters below, and were brought into position when the concrete had been placed in the lower half of

the pile. The hinged shutters did not meet at the top of the pile, a gap being left for placing the concrete. The top face of the concrete in the gap was finished by hand. The shuttering for the cylindrical cavity was a collapsible core. The lower ends of the piles, which are flat, are protected by welded steel plates.

driven after the site had been dredged to the general level of about 41 ft. below datum, that is to 34 ft. below low-water at ordinary spring tides.

Two 90-ft. floating pile-drivers, which could be converted to cranes, were brought by sea from Holland. Each was mounted on a pontoon 60 ft. wide and





Fig. 10.—First Stage of Construction of Caisson.

The cage of reinforcement bars for a pile was fabricated in sections on a trestle immediately over the cradle on to which it was lowered by hand.

When the concrete had hardened, the four pieces of shuttering were removed and the piles remained on the cradle (Fig. 6) before being transported by the site railway (Fig. 7) to the berth where they were placed on a barge (Fig. 8) carrying four piles at a time to floating pile-drivers (Fig. 9). The piles were

70 ft. long. When at anchor, the drivers could operate over an area 100 ft. by 40 ft. The hammers were 8½-ton single-acting steam hammers. About fifteen piles were driven weekly by each pile-frame. The bearing strata are gravel and clay, into which the piles were driven to a set of 80 blows to 12 in. when the drop of the hammer was 2 ft. The heads of the piles were cut off at the level of the seating of the precast frames carried by the piles, but the reinforcement projected



**Fig. 11.—Foreground : Caisson on Platform (Jacks to the right). Middle : Caisson Afloat (lower part of wall under Construction). Background : Upper part under Construction.**

3 ft. above this level so as to bond with cast-in-situ concrete forming the seating of the precast frames.

#### **Caissons.**

The two berths for casting caissons were immediately behind the pierhead trestle and each comprised two principal parts. In the first part a timber platform on steel beams (*Fig. 10*) was suspended by rods from four hydraulic jacks each of 120-tons capacity for the 40-ft. caissons and 70 tons for the 36-ft. caissons. The jacks were supported on a timber trestle.

The bottom and 24 ft. of wall of a caisson were cast on the platform. After seven days the platform was lowered and at high-water the caisson was floated to the second part of the berth where ballast concrete was added to increase the draught from 9 ft. to 15 ft. The wall was then constructed up to a height of 45 ft., and more ballast added to give a draught of 29 ft. The wall was then completed to a total height of 66 ft., the draught being 33 ft., and the caisson was towed to and temporarily sunk at a convenient place for storage. Some stages in the

construction of the caissons are seen in *Figs. 10 to 12.*

The construction of a caisson took about five weeks. Continuously-moving forms were used for the walls, the rate of construction being from 4 in. to 6 in. per hour. Concrete for the walls constructed

57 ft. below datum. Immediately before sinking the caisson, silt was removed from the hole by an 8-in. compressed-air pump, and gravel deposited through an 8-in. tremie and screeded by divers to form a level bed. Water was pumped from a caisson in storage and the caisson was




Fig. 12.—Caisson Being Towed, showing Moving Form.




Fig. 13.—Part of Pierhead and a Caisson in Position.

while on the platform was mixed at a plant at the casting berth and hoisted in wheelbarrows by a 15-cwt. mast-hoist. While the walls did not exceed 45 ft. high, concrete was placed by a 10-tons derrick crane having a 100-ft. jib and, when exceeding this height, by a 3-tons crane on a 30-ft. tower (*Fig. 11*).

At the permanent position of each caisson a hole was dredged to gravel about

towed to the permanent position into which it was manoeuvred by two craft just before high-water. The caisson was then sunk at the rate of about 1 ft. per minute by admitting water through two 10-in. valves. When grounded, the caisson was partly filled with sand. At this stage the wall projected about 3 ft. above high-water and was continued upwards by concrete cast in panel shutters.

# STEEL FORMS

The Multiple System of Interlocking  
**STEEL SHUTTERING**  
for in-situ concrete construction



**GUARANTEED HAND RIVETED  
CONSTRUCTION THROUGHOUT**

POSITIVELY NO WELDING

EACH UNIT A COMPLETE ASSEMBLY  
ENGINEERED WITH ACCURACY AND PRECISION

**STEEL FORMS** *will be on view at the*  
BUILDING EXHIBITION, OLYMPIA, NOV. 14-28,  
ON OUR STAND No. 342, ROW T

**A. A. BYRD AND CO. LIMITED**  
210 Terminal House, Grosvenor Gardens,  
London, S.W.1

'Phone : SLOane 5236

'Grams : Byrdicom, Wesphone, London



*-there's*  
**SGB**  
*again!*

MITCHAM, SURREY. Telephone MITCHAM 3400 (18 lines)  
Depots and Branches in all Principal Towns and Cities

Prince Albert Memorial, Hyde Park

*-the originators of tubular scaffolding!*






Fig. 14.—Part of Pierhead Trestle : Floating Mixer on left.

#### Precast Frames.

In the pierhead-trestle, berthing islands, and connecting trestles there are about 170 precast frames (Figs. 13 and 14), those in the pierhead-trestle weighing about 18 tons each and in the berthing islands 10 tons each. There are more than 1000 precast struts and gangways. Each frame was cast on a concrete base of the same shape as the elevation of the frame and projecting above the casting bed. Twenty bases were used. After the reinforcement had been placed, wooden side shutters were placed against the edges of the base which acted as a template for the mould. When a frame was sufficiently matured, it was taken on the site-railway to the same loading berth as the cylindrical piles, and thence by barge to the erection position. The precast struts were dealt with in the same manner.

The frames and struts on one side of the structure were lifted into position by a 30-tons floating crane, and the struts on the other side by a 3-tons floating crane.

Cylindrical steel caps (Fig. 13) attached to the top of the cylindrical piles supported the frame temporarily and also supported the staging and working platform and served as shuttering for the concrete cast in situ to support permanently the frame.

The contractors for the civil engineering work are Messrs. Christiani & Nielsen, Ltd., who also designed the civil engineering structures in collaboration with the Standard Oil Development Corporation with the exception of the approach which was designed by the Corporation. Construction commenced in January, 1950, and the first berths were completed in August, 1951; it is expected that the remainder of the work will be complete in the autumn of this year. The total cost of the civil engineering work is about £1,600,000. At the peak period of construction about 1250 workmen, 15 general foremen, 30 trades foremen, and 25 clerks, storekeepers, etc., were employed in addition to 25 civil and mechanical engineers.

## Coast Protection Works at Clacton.

COAST-PROTECTION works comprising concrete groynes and a sea-wall at Clacton-on-Sea are described by the Borough Engineer and Surveyor, Mr. W. Aiston, in a recent number of the *Journal of the Institution of Municipal Engineers*, from which the following is abstracted.

### The Main Groynes.

Owing to the deterioration of existing timber groynes, all new groynes are of

The concrete in the core of the wall is 1:2:4 with gravel aggregate graded from  $1\frac{1}{2}$  in. to  $\frac{3}{4}$  in. The exposed faces are finished with 4-in. of 1:1 $\frac{1}{2}$ :3 concrete, the aggregate in which was, in the early parts of the work,  $\frac{3}{4}$ -in. granite chippings. Tests indicated that the resistance of gravel aggregate to abrasion from beach material was as good as that of the granite aggregate. The face of granite concrete was therefore omitted in




Fig. 1.—Typical Cross Section of Main Groyne.

concrete and are 310 ft. long (Fig. 1). At the landward end are a ramp and steps, and a sluice with timber planks by which the drift of sand and shingle can be partly controlled. Seaward from the sluice the groyne is of plain concrete and is of constant shape but decreasing size. The sides are vertical, and buttresses and steps are provided to break scour action. The toe-piles are 12-in. by 6-in. or 7-in. reinforced concrete sheet-piles with bird-mouth joints and 10 ft. to 15 ft. long. The groyne is divided into bays each 11 ft. 6 in. long keyed together by a tongue-and-groove joint for the full height. Dowel-bars 5 ft. long and  $1\frac{1}{4}$  in. diameter are provided at the bottom across each joint. Every third joint is an expansion joint having a  $\frac{1}{2}$ -in. gap filled with bituminised cork.

later parts of the work, and gravel graded from  $\frac{3}{4}$  in. to  $\frac{1}{4}$  in. used.

Each groyne was constructed within a cofferdam extending above high-tide level. Excavation was carried down to a firm clay, called platimore, and the concrete sheet-piles were driven. The six longitudinal reinforcement bars in each pile projected 5 in. above the head, and the ends were bent outwards to key into the 18-in. square capping beam. The shuttering for the concrete in the groyne was steel-faced timber and, where the 4-in. cover of fine granite concrete was provided, 18-in. by 12-in. sliding steel plates were used to separate the two concretes. The concrete was delivered to the shutters in 1-cu. yd. skips and was spread over the area of one bay.

The greatest amount of concrete to be

# Ritecure


THE RIGHT CURE FOR CONCRETE

## MEMBRANE CURING

Sales of "Ritecure" are backed by expert technical knowledge of efficient and economical concrete curing. Production is under the control of our laboratory where extensive tests and research are continually carried on to ensure the maintenance of the high standard of our products.

To ensure efficient application of "Ritecure," we have built up a large fleet of power-driven spray units specially designed for spraying "Ritecure." These are available for hire and are maintained by our fully-equipped service department.

**RITECURE SPRAYING UNIT READY FOR USE**




## STUART B. DICKENS

MANUFACTURER

LONDON OFFICE: 36 VICTORIA STREET, S.W.1  
TELEPHONE: ABBEY 4930

WORKS: OLD MILTON STREET, LEICESTER  
TELEPHONE: LEICESTER 30390

---



A general view of the new coking plant at the East Greenwich Gasworks, designed and constructed by Messrs. Simon-Carves, Ltd., for the South Eastern Gas Board. All the structures shown are supported on Simplex Concrete Cast-in-Situ Piles.

## **SIMPLEX CONCRETE PILES LTD.**

25 BRECHIN PLACE,

SOUTH KENSINGTON,

LONDON, S.W.7

Telephone: Fremantle 0035-6

---

placed in one bay was about 50 cu. yd. and the average time taken to place this amount was about  $7\frac{1}{2}$  hours when a 4-in. granite-concrete cover was provided and  $5\frac{1}{2}$  hours when using concrete of one quality only. In the part of the groyne at the steps about 170 cu. yd. of concrete were placed in about 22 hours. About 1250 cu. yd. of concrete were placed in the first groyne in addition to the concrete in the piles.

### Intermediate Groynes.

Intermediate groynes, which were constructed in 1942-43, are at about 330-ft.

forced concrete capping-beam. Each bay is 15 ft. long, adjoining bays being keyed together by a tongue-and-groove joint and seven  $1\frac{1}{4}$ -in. mild steel dowel-bars near the bottom. Allowance is made for expansion at alternate joints, in which a  $\frac{1}{2}$ -in. slab of bituminised cork is inserted. A water-seal is provided by a copper strip across the joint.

The length of the wall is 660 ft. in a straight length which for constructional purposes was divided into five parts each about 130 ft. long and each built within a steel sheet-pile cofferdam. At no time did work proceed on more than two parts.




Fig. 2.—Cross Section of Sea Wall.

intervals and extend 100 ft. seaward from the wall. They comprise 12-in. square reinforced concrete grooved piles from 15 ft. to 28 ft. long at 6-ft. centres. Reinforced concrete slabs 5 ft. 4 in. long and 11 in. by 5 in. in cross section fit in grooves in the piles.

### The Sea-wall.

The new sea-wall has three horizontal 10-in. steps in addition to a batter on the seaward face (Fig. 2). To protect the foundation against scour, 13-in. by 7-in. V-jointed reinforced concrete sheet-piles 10 ft. 6 in. long are driven to below mean low-water level in front of the wall. Above the piles is an 18-in. square rein-

forced concrete capping-beam. After excavating, the reinforced concrete sheet-piles were driven and the capping-beam constructed. The shuttering for the wall was a steel travelling shutter (Fig. 3) suspended inside a gantry by three jacks at both ends. The gantry moved on a track one rail of which was on the capping-beam and the other on the ground behind the wall. Striking, moving, and re-setting were completed in a few hours. The length of the shutter was 15 ft. 3 in., and overlapped the completed part of the wall by 3 in.

The wall is of 1:2:4 concrete. An immersion vibrator was used for compacting the concrete at the stepped sections of the wall, the remainder being

consolidated by treading and hand punning. In each 15-ft. bay there are about 50 cu. yd. of concrete which were placed in six hours. The cost of the sea-wall was about £35 per foot.

As it was possible to construct only a short length of sea-wall at present, tem-

each frame drove up to thirteen piles a day through about 2 ft. of beach material and 12 ft. of clay containing small clay stones, which caused difficulties in driving. Often by hard driving the piles displaced the stones, but in some cases the stones caused the piles to twist slightly or become




Fig. 3.—Travelling Shutter for Sea Wall.

porary protection of the remainder of the foreshore is provided by a wall of 13-in. by 7-in. reinforced concrete sheet-piles 21 ft. long driven 4 ft. below mean low-water level and stiffened by timber walings and struts bearing against timber piles. When the sea wall is extended the upper part of the piles will be cut off and a reinforced concrete capping-beam cast on top. Two pile-frames worked continuously on this temporary wall, and

inclined. The distorted piles have not been withdrawn because of the difficulty of so doing and redriving them plumb, and the only detriment to the wall is its appearance. When the construction of the sea-wall proceeds, the alignment will be trued by the capping-beam. The cost of this wall, including drains, timber piles and struts, was about £18 per ft.

The contractors were Messrs. G. Percy Trentham, Ltd.





# Winget

*5 T/H (7/5 cu. ft.) and 7 T/H (10/7 cu. ft.) Tilting Drum Mixers*


WINGET LTD. ROCHESTER KENT ENGLAND. TELEPHONE STROOD 7276



**TRIANCO**  
Telescopic Centers  
for  
ECONOMICAL  
CONSTRUCTION


24th  
Building  
Exhibition—  
**OLYMPIA**  
Nov. 14-28,  
1951

See our  
Stand No.  
293/4  
Row 'P'



No timber is required, no carpenters' workshop on site. No obstruction beneath. For solid Concrete or Hollow Tile floor and roof construction. Instantly-adjustable up to 15 ft., adaptable for larger spans. Invaluable also for repair work. On hire from stock. Write or 'phone.

**TRIANCO LTD. (D. 26)**  
Imber Court, East Molesey, Surrey  
'Phone: Emberbrook 3300 (4 lines)



Easy to work: no strain on operator

## JOHNSON *Internal* Concrete **VIBRATORS**

Illustrated is PETROL FLEX DRIVE [one of two types] Johnson Internal Vibrator. Vibration is confined to the "needle," thus ensuring long life of motor; imposes no strain on operator; all mechanical parts greased and sealed for life. Also Electric Flex Drive and Electric Stiff Shaft models available with 2½ in. & 1½ in. diam. needles. Write for Folder V24.



Reduces strain on operator

## SELF-PROPELLING **VIBRATING HAND SCREEN**

Where strength is needed on concrete slabs use the CHJ Vibrating Screenshot Unit. Consolidates 6 in. stiff concrete; produces excellent surface, smooth or rough (non-skid) at 6 ft. per min. (appx.). Finishing pass 10 ft. p.m. Folder S/24 gives performance details, etc.

Manufactured by

**C. H. JOHNSON (MACHINERY)  
LTD.**

V/S/24, ADSWOOD RD., STOCKPORT

Tel.: STOCKPORT 2642/5

or contact our nearest representative:

**LONDON:** Prospect 7671. **BRISTOL and SOUTH WALES:** (Bristol) Lulgate 277. **MIDLANDS:** 40 Onar Road, Stoke, Coventry. **LANCS. and CHES:** Irby 1410. **YORKS, NORTHUMBERLAND and DURHAM:** Otley 2463. **N. WALES and SHROPSHIRE:** Chester 22037. **SCOTLAND:** 143 Hilsdie Rd., Mansewood, Glasgow.

## Effect on Concrete of Chemicals used in Consolidating Soils.

WE have submitted to Imperial Chemical Industries, Ltd., an inquiry on the effect on concrete of the chemicals commonly used in consolidating soils, and as this is a matter of general interest we give their reply below.

"The chemicals most frequently used in two-fluid injection processes for chemically consolidating loose ground or porous strata are solutions of sodium silicate and calcium chloride. Sodium carbonate is sometimes added to the sodium silicate solution. There are also single-fluid processes based on sodium silicate solutions containing chemicals such as sodium bicarbonate, sodium aluminate, and borax. In the two-fluid process the end product is usually considered to be a complex mixture of gels of hydrated silica and sodium silicate with a small amount of calcium silicate, whilst in the single-fluid process gels of hydrated silica predominate. The formation of any calcium

silicate by interaction between calcium chloride and sodium silicate will be accompanied by the formation of an equivalent quantity of sodium chloride.

"In our opinion the end products of these reactions can have no effect either on precast concrete or on concrete placed in position in contact with them. These end-products are inert and neutral, and are not able to change in course of time into anything that could damage concrete. Neither do we think that any sodium silicate or calcium chloride that may have been added in excess, or have failed to react, will have any significant effect on precast concrete, since neither chemical is harmful to concrete; sodium silicate in fact has a beneficial hardening effect. We should not be so confident if sulphates were used in any of these processes (for example aluminium sulphate has, we believe, been used on occasion in the single-fluid process) since Portland cement

## STEEL TRENCH SHEETING

(Regd. design  
No. 850839)

**Prompt  
Delivery**

For the temporary lining of trenches and foundations. *Prices and full particulars on application to:—*

**DORMAN LONG & CO. LTD., SHEET DEPT.  
AYRTON WORKS, MIDDLESBROUGH**

London Office: Terminal House, 52 Grosvenor Gardens, S.W.1

# DORMAN LONG

concrete in contact with soluble sulphates is liable to suffer disintegration. With regard to the effect, if any, that sodium silicate or calcium chloride could have on concrete placed in position in contact with them, as both chemicals accelerate the setting and hardening processes of Portland cement it would no doubt be possible for a very thin layer of the concrete in contact with the consolidated ground to set and harden somewhat more quickly than the rest of it. Even if this did happen we do not think it would have any significant effect on the concrete as a whole, for it is likely that the amounts

of sodium silicate or calcium chloride liable to be present after a consolidation process are so small that their effects can be ignored. There is in our opinion no danger of concrete in contact with ground containing traces of sodium silicate, gels of sodium silicate or silica, calcium chloride, sodium chloride, sodium carbonate, or sodium bicarbonate suffering any slow attack over periods of years.

"Most of the information given in this letter is clearly a matter of opinion and, while our opinion is given in good faith, we cannot accept responsibility should time prove it to be wrong."

## Composite Trussed Beams.



Fig. 1.

To reduce the weight of precast concrete beams of long span, Dr. Ernst Deutsch describes in "Beton-und Stahlbetonbau" for March, 1951, a type of composite concrete and steel trussed beam used for the roof of a factory (Fig. 1). The compression flange is a rectangular precast concrete beam 13½ in. deep and 12 in. wide reinforced with four ¾-in. bars in the top and bottom. The tensile flange and vertical members are welded steel channels. The trussed beams span about 33 ft. and are designed for a total load of 1344 lb. per ft. The tensile stress in the bottom tie is 19,900 lb. per square inch. The fabrication of the trussed beams is simple. The channels are welded together first and are then placed upside down in the mould for the concrete beam; plates welded to the ends of the channels enable the steel frame to stand in the mould. The trussed beams are at 16 ft. centres and support precast slabs.

Loading tests were made on two prototypes of the trussed beams to determine the factor of safety in bending and shear, and to prove the stiffness of the composite member and the effectiveness of the bond between the steel channels and the concrete beam. The results of the tests were satisfactory, although under unsymmetrical loading it was possible to cause local overstressing of the concrete.

This type of composite trussed beam effects a great saving of steel compared with a steel truss, and a great saving of weight compared with a concrete beam.

Specialities Allied to—

### CONCRETE & BUILDING PRODUCTS

Including Accelerators, Retarders, Hardeners, Waterproofer, Oilproofers, Cement Paints, etc.

For full particulars please write

### ALLIED BUILDING COMMODITIES

LITTLE ROYD, HUDDERSFIELD.

## MISCELLANEOUS ADVERTISEMENTS.

*Situations Wanted, 3d. a word: minimum 7s. 6d. Situations Vacant, 4d. a word: minimum 10s. Other miscellaneous advertisements, 4d. a word: 10s. minimum. Box number 1s. extra.*

**Advertisements must reach this office by the 23rd of the month preceding publication.**

## SITUATIONS VACANT.

## MINISTRY OF WORKS

Drawing Office Staff are required in the Structural Engineering Division, for duty in London, Risley (Warrington) and principal provincial cities. Hostel accommodation is available for men at Risley. LONDON SALARY: STRUCTURAL ENGINEERING ASSISTANTS, £340-£575 per annum. Minimum is linked to age 21 with £20 additional for each year above, up to a maximum entry rate of £480 per annum. LEADING STRUCTURAL ENGINEERING ASSISTANTS, £570-£675 per annum. Rates outside London are slightly lower. Applicants should be experienced in design and/or detailing of either reinforced concrete or structural steelwork. The work is varied and not confined to standard schemes. Although these are not established posts, some of them have long term possibilities, and competitions are held periodically to fill established vacancies. Apply in writing, stating age, nationality, full details of experience, and locality preferred, to: CHIEF STRUCTURAL ENGINEER, W.G. 10/BN., Ministry of Works, Abell House, John Islip Street, London, S.W.1.

**SITUATIONS VACANT.** Experienced designers required for East Africa by long-established company of reinforced concrete specialists employed primarily on design of commercial structures. Unmarried men preferred. Salary commensurate with experience and qualifications. Box "AG/106," c/o 95 Bishopsgate, London, E.C.2.

**SITUATIONS VACANT.** Reinforced concrete designers and detailers wanted for Southern Rhodesia and Union of South Africa. Candidates should have had at least five years' experience of competitive designing. Free passages. Salary according to experience and qualifications. Details in confidence to Box "AG/107," c/o 95 Bishopsgate, London, E.C.2.

**SITUATIONS VACANT.** Two reinforced concrete detailers required for permanent staff, Westminster. Salary £600-£750, according to experience. Applications, which should state age, details of experience, and salary required, to Box 2494, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Consulting engineers, Westminster, have vacancy for senior reinforced concrete detailer on their permanent staff. Commencing salary £850 p.a. Applicants must have had not less than five years' experience in a good reinforced concrete drawing office in a reasonably responsible position. Applications, which will be treated in confidence, stating age and experience, to be sent to Box 2495, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Draughtsmen with experience in reinforced concrete and structural steelwork required by London consultants. Desirable age range 25 to 35, but applications will be considered on experience irrespective of age. Box 2504, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Engineer required in London office for the design of prestressed concrete structures. Only men with experience in this class of work will be considered. State age, experience, and salary required, to TWISTEL REINFORCEMENT, LTD., 43 Upper Grosvenor Street, London, W.1.

**SITUATION VACANT.** A British firm of contractors and civil engineers operating in Malaya and Borneo require a qualified engineer sufficiently experienced to take charge of major contracts. Write, with full particulars, to Box "AG/168," c/o 95 Bishopsgate, London, E.C.2.

**SITUATIONS VACANT.** Established firm of reinforced concrete engineers and designers operating in the provinces is considering opening up a prestressed concrete department. Applications are invited from young engineers experienced in this material to take charge of developments in this department. Please write in first place giving particulars of training, experience, and salary required. Box 2500, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Required for Karachi, Pakistan, one chief designing engineer with sound knowledge of reinforced concrete design, and two assistant engineers, by well-known civil engineering contractor. First-class salaries for right men. For interview in London, send particulars of age, education, training, qualifications, and experience, etc., stating whether single or married and when available. Box 2501, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Engineers experienced in reinforced concrete construction required in Bombay and Singapore by well-known civil engineering contractor. First-class salaries for right men. For interview in London, send particulars of age, education, training, qualifications, and experience, etc., stating whether single or married and when available. Box 2502, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Reinforced concrete designer/draughtsman required by consulting engineers, Westminster. Range of work is varied and post is not temporary. Experience in leading a small team will influence remuneration, as this will be based on qualifications and experience. Salary range contemplated but subject to consideration is £600-£700. Please indicate experience and previous employment and any particular qualifications, to Box 2503, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Purchasing supervisor for international construction firm's London office. Engineering graduate preferred with general knowledge of mechanical equipment, purchasing experience, and administrative ability. Age 35-50. Good salary commensurate with experience. Give full details of qualifications and education in application to Box "SP/48," c/o 95 Bishopsgate, London, E.C.2.

**SITUATIONS VACANT.** Detailer draughtsmen with experience in reinforced concrete work required by consulting engineer at Bayswater. Permanent positions, good salary, and prospects. Apply with full details, to CLARKE, NICHOLLS & MARCEL, 21 Westbourne Grove, London, W.2, or telephone Bayswater 6816 for appointment.

**SITUATIONS VACANT.** Assistant engineers or designers wanted at once for consulting engineers' office in London. Must have some experience in design of reinforced concrete structures, preferably road bridges. Age 25 to 35. Salary according to qualifications and experience. Write, giving full particulars of qualifications and experience, to Box No. 5225, c/o CHARLES BARKER & SONS, LTD., 31 Budge Row, London, E.C.4.

**SITUATION VACANT.** The Concrete Development Co., Ltd., require a designer-draughtsman at their works at Iver, Bucks., who will also carry out other duties such as concrete control and testing. The work will deal mainly with prestressed concrete, and an educational standard to Higher National Certificate level is necessary. Write, stating age, experience, and salary required, to the CONCRETE DEVELOPMENT CO., LTD., 1 Queen Anne's Gate, London, S.W.1.

**SITUATIONS VACANT.** Junior and senior draughtsmen, with good experience in all branches of reinforced concrete, wanted for consulting structural engineer's office. Experience in structural steelwork an advantage. Salary according to age and experience. Please apply in writing to F. J. SAMUEL, 8 Hamilton Place, London, W.1.

**SITUATION VACANT.** Engineer, with degree or equivalent in engineering, required by the British Cast Concrete Federation to assist in development work connected with concrete vibrators, etc., at research laboratories of the Cement and Concrete Association, Wexham Springs, near Slough. Applicants should preferably be under 26 years of age, but if older should have had experience in allied fields. Applications, giving full details, including qualifications, age, experience, ability, and commencing salary expected, should be addressed in writing to SECRETARY, B.C.C.F., 17 Amberst Road, Ealing, W.13.

(Continued on page liiv.)



# MISCELLANEOUS ADVERTISEMENTS

(Continued from page liii.)

## PURCHASING EXECUTIVE.

An engineer with administrative ability and extensive experience in purchasing heavy engineering equipment and machinery is required to head department of large petroleum refinery construction and engineering firm in City of London. Salary will be fully commensurate with the requirements of this important position in expanding organisation, and will be dependent on experience and qualifications, of which fullest details may be written in confidence to Box 2505, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

WELL-KNOWN ANGLO-AMERICAN ENGINEERING AND CONTRACTING FIRM in the City of London requires for oil refinery work:—

**TWO SENIOR REINFORCED CONCRETE DESIGNERS**—Chartered Structural and/or Chartered Civil Engineer, minimum of 8-10 years' experience in design of continuous Reinforced Concrete structures, heavy foundation design including piling, raft foundation and sheet piling. Must be able to assume responsibility and direct 2-3 draughtsmen.

**ONE SENIOR ARCHITECTURAL DESIGNER/DRAUGHTSMAN.** Should have minimum 10-15 years' experience in building and architectural layout. Must be entirely familiar with building materials, heating and ventilating details.

**TWO PRESSURE VESSEL DESIGN-DRAUGHTSMEN.** 8-10 years' experience in draughting office and shop of Welded Pressure Vessel design, construction and inspection. Must be completely familiar with A.P.I./A.S.M.E. Codes and Standards.

**FOUR PIPING LAYOUT DESIGNERS.** H.N.C. or equivalent, with minimum of 10 years' piping experience; must be capable of designing complete pipework installation for refinery and chemical plants to A.S.A. Standards. Applicants must be able to direct 4-5 draughtsmen.

**ONE MECHANICAL EQUIPMENT ENGINEER.** Grad. I.Mech.E. Must be familiar with British equipment manufacturers, thorough knowledge of design and construction of compressors, blowers, turbines, centrifugal and reciprocating pumps. Minimum 10 years' experience, preferably within oil refinery field.

**ONE HEAT EXCHANGER DESIGNER/DRAUGHTSMAN.** H.N.C. or equivalent. 8-10 years' experience in draughting office and shop. Must be familiar with A.P.I. Code and T.E.M.A. Standards. Capable of turning out design drawings from Data Sheets and Specifications.

Excellent salaries and opportunities are offered to men of ability and ambition. Give full details of age, experience, etc., to Box 2507, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Senior reinforced concrete designer required by expanding Midlands firm of engineers and contractors. Pension scheme in operation. Box 2506, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Simon-Carves, Ltd., have several vacancies for experienced draughtsmen in the following fields: Boiler pipework and general power plant design, coke oven and by-products plant design, coal washing and mechanical handling plant design, general chemical plant layout and design, reinforced concrete and structural steelwork design. Excellent working conditions and prospects are offered for men with good experience and ability. Canteen, welfare, and sports facilities. Pension scheme in operation. Please send full details of experience, age, and training, and quoting PE/701, to PERSONNEL & TRAINING MANAGER, SIMON-CARVES, LTD., Cheadle Heath, Stockport.

**SITUATION VACANT.** Position of chief clerk is offered by Anglo-American engineering and contracting firm in City of London. Duties include responsibility for the operation of the blue-print and "ditto" office, for the filing, release and control of drawings, the recording of foreign prints, distribution and requisition of office supplies. Write Box SP/133, c/o 95 Bishopsgate, London, E.C.2.

## SITUATION WANTED.

**SITUATION WANTED.** Reinforced concrete. Gentleman with extensive experience in all branches seeks change. Responsible position required, preferably involving representation in South Wales, where a connection already exists among architects and Councils. Box 2508, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

## FOR SALE.

**FOR SALE.** Sacks, bags, and curing cloths for sale. You want the best type and quickest delivery. Write JOHN BRAYDON, LTD., 26 The Highway, London, E.1. Telephone: ROYAL 1044.


**FOR SALE.** 60 tons of Sommerfeld mesh wire with 1/2 in. rods at 9 in. centres. PIKE BROS., Colnbrook, Bucks. Telephone: 175.

## PATENT.

**PATENT.** The Proprietor of British Patent No. 601398 for "IMPROVEMENTS IN AND RELATING TO SHUTTERS FOR USE IN BUILDING CONSTRUCTIONS", desires to enter into negotiations with a firm or firms for the sale of the patent or for the grant of licences thereunder. Further particulars may be obtained from MARKS & CLERK, 57 & 58, Lincoln's Inn Fields, London, W.C.2.

## WANTED.

**WANTED.** "Concrete and Constructional Engineering." Copies published since 1939. Complete sets or odd copies. Good price paid by an Institution which requires them for its library. Box 2499, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1. **WANTED URGENTLY.** Complete sets or single copies of "Concrete and Constructional Engineering" and "Cement and Lime Manufacture" 1940-1950. Offers, to STECHERT-HAFNER, 2 Star Yard, Carey Street, London, W.C.2.





*They took their time in those days*



Bodiam Castle



29

*...But when working against the clock use*

**417 CEMENT<sup>®</sup>**

**QUICK SETTING  
EXTRA RAPID-HARDENING**



Full particulars of '417 Cement' will be sent on application to:—

**THE CEMENT MARKETING COMPANY LIMITED**

PORTLAND HOUSE · TOTHILL STREET · LONDON · SW1

G. & T. EARLE LTD · WILMINGTON · HULL

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD · PENARTH · GLAM

Every  
well-planned road  
laid in  
**Reinforced Concrete**  
is a step nearer  
to national  
highway perfection

**BRC**

REINFORCEMENT FOR ROADS

**THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD**

*London, Birmingham, Bristol, Leeds, Leicester, Manchester, Newcastle, Sheffield, Cardiff, Glasgow,  
Dublin, Belfast*

M-W.596